



UNDRGRD C MD
271 FT.

COMMUNICATIONS VAULT
1.0 EACH

UNDRGRD C MD
609 FT.

I-74

N. 1350TH AVE. (CH 32) UNDRGRD C MD
571 FT. (PUSHED)
UNDER ROADWAY
ALONG STEEP TERRAIN

UNDRGRD C MD
132 FT. N. 1350TH AVE. (CH 32)

SCHEDULE OF QUANTITIES		
ITS FIBER (WOODHULL TO MOLINE) - SHEET 41		
UNDERGROUND CONDUIT, MULTI-DUCT, 7-16MM MICRODUCTS	FOOT	1583.0
FIBER OPTIC CABLE 96 FIBERS, SINGLE MODE	FOOT	1633.0
COMMUNICATIONS VAULT	EACH	1.0

Imagery Date: 9/12/2011 1994

41°20'44.07" N 90°19'56.39" W elev 790 ft

Eye alt 2791 ft

FILE NAME =	USER NAME = keithbr	DESIGNED -	REVISED -
ct:\notes\68b04 fiber plans\68b04\68B04	- Woodhull to Moline (1-95) - Final 4-30-12.dgn	DRAWN -	REVISED -
	PLOT SCALE = 164.7568' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/1/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FIBER OPTIC CONDUIT AND CABLE PROJECT
I-74 (FROM WOODHULL TO MOLINE) CONTINUED

SCALE: SHEET NO. 41 OF 62 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR	D4 FIBER OPTIC 2013	HENRY/ROCK ISL	96	44
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68B04	

Google earth