

SCHEDULES OF QUANTITIES

CLASS B PATCHING, 10" (CONTINUED)

STATION	DIRECTION	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS 44201299 (each)	SAW CUTS 44213200 (ft)	TIE BARS 1/2" 44213198 (each)	PAVEMENT FABRIC 44213100 (sq. yd)
				TYPE I 10" (sq. yd)	TYPE II 10" (sq. yd)	TYPE III 10" (sq. yd)	TYPE IV 10" (sq. yd)				
118+52.00	Right Truck	6	8	0.0	5.3	0.0	0.0	12	36.0	0	0.0
118+90.00	Right Truck	6	11	0.0	7.3	0.0	0.0	18	45.0	0	0.0
119+05.00	Right Truck	6	11	0.0	7.3	0.0	0.0	18	45.0	0	0.0
119+29.00	Right Truck	6	22	0.0	14.7	0.0	0.0	40	78.0	0	0.0
119+71.00	Right Truck	6	22	0.0	14.7	0.0	0.0	40	78.0	0	0.0
120+02.00	Right Truck	6	11	0.0	7.3	0.0	0.0	18	45.0	0	0.0
120+07.00	Right Truck	6	11	0.0	7.3	0.0	0.0	18	45.0	0	0.0
120+48.00	Left Truck	6	22	0.0	14.7	0.0	0.0	40	78.0	0	0.0
120+90.00	Right Truck	10	39	0.0	0.0	0.0	43.3	74	137.0	0	43.3
121+11.00	Right Truck	6	22	0.0	14.7	0.0	0.0	40	78.0	0	0.0
121+14.00	Right Truck	6	22	0.0	14.7	0.0	0.0	40	78.0	0	0.0
120+88.00	Left Truck	6	22	0.0	14.7	0.0	0.0	40	78.0	0	0.0
209+90.00	Car	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
217+30.00	Car	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
218+76.00	Car	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
219+18.00	Car	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
219+55.00	Car	6	16	0.0	10.7	0.0	0.0	28	60.0	0	0.0
220+00.00	Car	20	16	0.0	0.0	0.0	35.6	42	88.0	20	35.6
221+16.00	Car	8	16	0.0	14.2	0.0	0.0	28	64.0	0	0.0
118+52.00	Truck Lot	103	2	0.0	0.0	22.9	0.0	0	212.0	103	22.9
123+49.00	Exit Lane	34	18	0.0	0.0	0.0	68.0	64	122.0	34	68.0
GRAND TOTALS				0.0	999.0	22.9	404.9	2861.0	7156.5	544.0	427.8
ROUND TO				0.0	1000.0	25.0	405.0	2865.0	7160.0	545.0	430.0
				(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)	(each)	(ft)	(each)	(sq. yd)