

F.A. RY.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	7
STA.		TO STA.		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
* SANGAMON AND CHRISTIAN				

LOCATION OF WORK	CHRISTIAN COUNTY		SANGAMON COUNTY	
	80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE	
	ROADWAY	STRUCTURES	ROADWAY	
	STA. 1415+00.00 TO STA. 1665+04.46	SNO11-2514 SNO11-2515 SNO11-7052 SNO11-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
28100125	STONE RIPRAP, CLASS B3	SQ YD	5,309	3,329		1,980
28200200	FILTER FABRIC	SQ YD	17,249	7,804	7,465	1,980
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	362,836	247,201		115,635
30201500	LIME	TON	7,256.6	4,944.0		2,312.6
31101200	SUBBASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	8,481	1,149		7,332
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	29,676.7	20,077.8		9,598.9
35100300	AGGREGATE BASE COURSE, TYPE A 4"	SQ YD	80	80		
35100900	AGGREGATE BASE COURSE, TYPE A, 10"	SQ YD	56,922	39,158		17,764
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	4,865	3,781		1,084
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	2,946.0	1,952.0		994.0
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	9,821	3,888		5,933
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	29,463	11,663		17,800
40300500	COVER COAT AGGREGATE	TON	491.0	194.0		297.0
40300600	SEAL COAT AGGREGATE	TON	245.5	97.0		148.5

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 03/06/2012

DRAWN BY: B.J.D.
CHECKED BY: J.M.M.

Default L:\BID\10306601\Drawings\0672829-011-500.dgn 4/25/2012