

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	8
STA.		TO STA.		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
* SANGAMON AND CHRISTIAN				

LOCATION OF WORK	CHRISTIAN COUNTY		SANGAMON COUNTY	
	80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE	
	ROADWAY	STRUCTURES	ROADWAY	
	STA. 1415+00.00 TO STA. 1665+04.46	SN011-2514 SN011-2515 SN011-7052 SN011-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	514.7	288.5		226.2
40600300	AGGREGATE (PRIME COAT)	TON	65.8	65.8		
40600625	LEVELING BINDER (MACHING METHOD), N50	TON	1,126.3	1,126.3		
40600895	CONSTRUCTING TEST STRIP	EACH	6	3		3
40600990	TEMPORARY RAMP	SQ YD	436	258		178
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	969.7	969.7		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,834.3	2,834.3		
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	35,072	30,240		4,832
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	7,922	1,011		6,911
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	215,383	148,214		67,169
44000100	PAVEMENT REMOVAL	SQ YD	85,715	44,904		40,811
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,859	507		1,352
44004250	PAVED SHOULDER REMOVAL	SQ YD	6,897	2,164		4,733
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	1,500	1,500		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A  
DATE: 03/06/2012

DRAWN BY: B.J.D.  
CHECKED BY: J.M.M.

D:\csoft\1\AD01\030606\Drawings\sheet\sa\0672829-ah1-500.dgn  
4/25/2012