

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	11
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ILLINOIS	FED. AID PROJECT	
* SANGAMON AND CHRISTIAN				

LOCATION OF WORK	CHRISTIAN COUNTY		SANGAMON COUNTY	
	80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE	
	ROADWAY	STRUCTURES	ROADWAY	
	STA. 1415+00.00 TO STA. 1665+04.46	SNO11-2514 SNO11-2515 SNO11-7052 SNO11-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
542D1069	PIPE CULVERTS, CLASS D, TYPE 2 24"	FOOT	105	105		
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	576	329		247
5421D036	PIPE CULVERTS, CLASS D, TYPE 1 36" (TEMPORARY)	FOOT	50	50		
5421D048	PIPE CULVERTS, CLASS D, TYPE 1 48" (TEMPORARY)	FOOT	107			107
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2			2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	13	9		4
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	77	62		15
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	5	5		
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	8	6		2
54214731	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 36"	EACH	6	6		
54215547	METAL END SECTIONS 12"	EACH	10	10		
54215550	METAL END SECTIONS 15"	EACH	36	26		10
54215553	METAL END SECTIONS 18"	EACH	2	2		
54215559	METAL END SECTIONS 24"	EACH	6	6		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A  
DATE: 03/06/2012

DRAWN BY: B.J.D.  
CHECKED BY: J.M.M.

D:\p\p\030660\p\c\shuett\0672829-shr-500.dgn  
4/25/2012