

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	13
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ILLINOIS FED. AID PROJECT		
* SANGAMON AND CHRISTIAN				

LOCATION OF WORK				CHRISTIAN COUNTY		SANGAMON COUNTY
				80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE
SUMMARY OF QUANTITIES				ROADWAY	STRUCTURES	ROADWAY
				STA. 1415+00.00 TO STA. 1665+04.46	SNO11-2514 SNO11-2515 SNO11-7052 SNO11-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00
				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
60100945	PIPE DRAINS 12"	EACH	250	125		125
60100955	PIPE DRAINS 15"	EACH	250	125		125
60100965	PIPE DRAINS 18"	EACH	250	125		125
60107600	PIPE UNDERDRAINS 4"	FOOT	130,062	89,351		40,711
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	4,038	2,725		1,313
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10			10
60222805	MANHOLES, TYPE A, 5' -DIAMETER, WITH MEDIAN INLET (604106)	EACH	46	15		31
60238305	INLETS, TYPE A, WITH MEDIAN INLET (604101)	EACH	2	2		
60246805	MEDIAN INLET (604106)	EACH	8	8		
61100605	MISCELLANEOUS CONCRETE	CU YD	50	30		20
61101007	STORM SEWERS PROTECTED, CLASS A, 6"	FOOT	1,500	900		600
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	500	300		200
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	5,000	3,000		2,000
61101017	STORM SEWERS PROTECTED, CLASS A, 15"	FOOT	1,000	600		400

Default: L:\1007\10306560\Draw\shewers\0372829-shr-500.dgn
 7/23/2012

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A
 DATE: 03/06/2012
 DRAWN BY: B.J.D.
 CHECKED BY: J.M.M.