

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	18
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ILLINOIS FED. AID PROJECT		
* SANGAMON AND CHRISTIAN				

LOCATION OF WORK	CHRISTIAN COUNTY		SANGAMON COUNTY
	80% FEDERAL / 20% STATE		80% FEDERAL / 20% STATE
	ROADWAY	STRUCTURES	ROADWAY
	STA. 1415+00.00 TO STA. 1665+04.46	SNO11-2514 SNO11-2515 SNO11-7052 SNO11-7053 MINOR CIP STRUCTURES	STA. 0+00.00 TO STA. 130+00.00

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0001	0008	0001
X 80400100	ELECTRIC SERVICE INSTALLATION	EACH	8	4		4
X 81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	1,814	907		907
X 81028780	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3 1/2" DIA.	FOOT	32	16		16
X 81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	13,287	6,644		6,643
X 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	79	40		39
X 82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	8	4		4
X 83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	79	40		39
X 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	79	40		39
X 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	316	158		158
84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	21	11		10
84200804	REMOVAL OF POLE FOUNDATION	EACH	21	11		10
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2	1		1
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2	1		1
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2	1		1

X SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N/A
DATE: 03/06/2012

DRAWN BY: B.J.D.
CHECKED BY: J.M.M.

Default L:\DOT\030660\Draw\Sheets\0672829-sht-500.dgn 4/25/2012