

| F.A. RTE.                                       | SECTION     | COUNTY      | TOTAL SHEETS | SHEET NO. |
|---|-------------|-------------|--------------|-----------|
| 75  | 84-12; 11-3 | •           | 729          | 43        |
| STA. N/A  |             | TO STA. N/A |              |           |
| FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT |             |             |              |           |
| • SANGAMON AND CHRISTIAN                        |             |             |              |           |

**TREE REMOVAL SCHEDULE**

| STATION / LOCATION              | OFFSET        | TREE DIAMETER BASED ON 2004 SURVEY (INCHES) |    | TREE REMOVAL (6-15 UNITS) 1/2" PER YEAR (UNITS)                                       | TREE REMOVAL (OVER 15 UNITS) 1/2" PER YEAR (UNITS) | TREE REMOVAL ACRES (ACRES) |
|---------------------------------|---------------|---|----|---|--|----------------------------|
|                                 |               |   |    | DIAMETER BASED ON 2004 SURVEY TO 2012 CONSTRUCTION YEAR ASSUMING 1/2" GROWTH PER YEAR |  |                            |
| IL RTE 29 (CHRISTIAN COUNTY)    |               |   |    |   |  |                            |
| 1432+24.22                      |               | 161.37                                      | LT | 14  | 18   |                            |
| 1453+35.96                      |               | 686.65                                      | LT | 42  | 46   |                            |
| 1636+94.90                      |               | 119.60                                      | LT | 6,6,6   | 30   |                            |
| 1641+00.75                      |               | 124.96                                      | LT | 14  | 18   |                            |
| 1643+38.22                      | TO 1644+60.59 |   | LT |   |  | 0.10                       |
| 1653+37.91                      | TO 1665+04.46 |   | LT |   |  | 1.30                       |
| IL RTE 29 (SANGAMON COUNTY)     |               |   |    |   |  |                            |
| 0+00.00                         | TO 0+17.56    |   | LT |   |  | 0.10                       |
| 31+24.15                        | TO 38+04.61   |   | LT |   |  | 0.50                       |
| 65+73.14                        | TO 75+41.76   |   | LT |   |  | 0.80                       |
| 77+50.25                        | TO 79+71.11   |   | LT |   |  | 0.30                       |
| 84+81.58                        | TO 97+89.50   |   | LT |   |  | 1.40                       |
| TR 73 (CHRISTIAN COUNTY)        |               |   |    |   |  |                            |
| 192+35.58                       |               | 24.43                                       | RT | 40  | 44   |                            |
| 192+93.01                       |               | 27.45                                       | LT | 6   | 10   |                            |
| 195+10.12                       |               | 22.39                                       | RT | 30  | 34   |                            |
| CH21 (CHRISTIAN COUNTY)         |               |   |    |   |  |                            |
| 401+85.92                       |               | 39.64                                       | RT | 4   | 8  |                            |
| TR 63/TR74 (CHRISTIAN COUNTY)   |               |   |    |   |  |                            |
| 107+28.19                       |               | 27.85                                       | LT | 12,12   | 32   |                            |
| TR 299 (SANGAMON COUNTY)        |               |   |    |   |  |                            |
| 891+47.58                       |               | 18.19                                       | LT | 10  | 14   |                            |
| 893+39.85                       |               | 20.43                                       | LT | 30  | 34   |                            |
| TOTALS ADJUSTED FOR TREE GROWTH |               |   |    | 62  | 226  | 4.50                       |

SHT01  
L:\BD01\0306601\draw\sheets\0306601\Draw\72829-sht-Schedule.dgn  
4/25/2012

| REVISIONS |      |
|-----------|------|
| NAME      | DATE |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |
|           |      |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**  
TREE REMOVAL

SCALE: N/A  
DATE: 03/06/2012

DRAWN BY: K.E.J.  
CHECKED BY: J.M.M.