CONTRACT NO. 72829

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	51
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		

* SANGAMON AND CHRISTIAN

ENTRANCE SCHEDULE

STATION/LOCATION		AGGREGATE SURFACE COURSE, TYPE B (TON)	TEMPORARY ACCESS (PRIVATE ENTRANCE) (EACH)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) (EACH)	TEMPORARY ACCESS (ROAD) (EACH)	TEMPORARY ACCESS (FIELD ENTRANCE) (EACH)
IL RTE 29						
STA. 1472+00.00	RT	73				1
STA. 1478+70.00	LT	57				1
STA. 1498+70.00	LT	116				1
STA. 1511+91.25	LT	76				1
STA. 1511+91.25	RT	133				1
STA. 1568+00.00	LT	48				1
STA. 1570+00.00	RT	150				1
STA. 00+10.00	RT	53				1
STA. 31+44.28	LT	396				1
STA. 82+46.26	LT	25				1
STA. 99+29.19	RT	186				1
TR 81						
STA. 93+08.96	LT	29				1
STA. 95+47.93	RT	33				1
STA. 99+37.60 (MOT 2)	-				1	
STA. 102+98.10	LT	35				1
STA. 102+9810	RT	35				1
TR 73						
STA. 190+58.77	LT	33				1
STA. 190+58.77	RT	41				1
STA. 192+77.93 (MOT 2)	-				1	
STA. 194+43.72	LT	16	1			
STA. 194+95.71	RT	13	1			
STA. 197+15.00	RT	25				1
STA. 203+61.47	LT	33				1
STA. 203+61.47	RT	33				1
TR 73 CONNECTOR						
STA. 295+55.74	LT	29		1		
STA. 296+37.60	LT	26		1		
STA. 297+55.99	RT	39				1
CH 21						
STA. 397+20.00	RT	29				1
STA. 403+8.98	RT	13	1			
STA. 403+61.21	RT	20				1
STA. 404+23.00	LT	30				1
TR 69 (IL RTE 29 STATIONING)						
STA. 1515+32.42	LT	12				1
STA. 1515+32.42	LT	11				1
CH 23						
STA. 481+58.90	RT	17				1
STA. 483+47.00	LT	62				1
STA. 485+00.00	RT	154				1
STA. 507+00.00	LT	41				1
STA. 507+00.00	RT	28				1

STORM SEWER SCHEDULE

STATION / LOCATION		STORM SEWER, CLASS A, TYPE 1, 24" FT.	STORM SEWER, CLASS A, TYPE 2, 24" FT.	TRENCH BACKFILL CU. YD.
IL RTE 29				
1645+76.11	LT		94.21	41.94
1647+76.11	LT	195.65		
TOTALS		196	94	42

ENTRANCE SCHEDULE (CONT.)

STATION/LOCATION		AGGREGATE SURFACE COURSE, TYPE B (TON)	TEMPORARY ACCESS (PRIVATE ENTRANCE) (EACH)	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) (EACH)	TEMPORARY ACCESS (ROAD) (EACH)	TEMPORARY ACCESS (FIELD ENTRANCE) (EACH)
IL RTE 29						
STA. 508+12.37	LT	41				1
STA. 508+12.37	RT	20	1			
TR 88						
STA. 580+68.27	RT	54				1
STA. 589+50.19	LT	92				1
STA. 590+43.21 (MOT 2)	LT				1	
STA. 604+00.00	LT	31				1
STA. 604+00.00	RT	26				1
TR 63/74 CONNECTOR						
STA. 699+44.75 (MOT 2)	-				1	
TR 63/74 NORTH						
STA. 96+22.58	RT	29				1
STA. 102+70.00	LT	32				1
STA. 103+64.27	LT	14	1			
TR 63/74 SOUTH						
STA. 97+00.00	RT	28				1
STA. 97+00.00	LT	28				1
STA. 105+40.48	RT	28				1
STA. 107+43.06	LT	38	1			
TR 321/486 CONNECTOR						
STA. 800+13.00 (MOT 2)	-				1	
TR 321/486						
STA. 94+50.00	LT	34				1
STA. 96+00.00	RT	33				1
STA. 103+00.00	LT	41				1
STA. 103+00.00	RT	33				1
TR 299						
STA. 890+38.12	LT	17	1			
STA. 892+40.96	LT	16	1			
STA. 893+87.33	RT	24				1
STA. 899+87.00 (MOT 1)	-				1	
STA. 906+32.49	LT	24				1
STA. 907+40.03	LT	27				1
STA. 907+40.03	RT	27				1
TR 299 NORTH FRONTAGE ROAD						
STA. 103+13.52	LT	28				1
STA. 104+84.99	LT	31		1		
TOTALS		2,946.0	8	3	6	50

TEMPORARY DRAINAGE SCHEDULE

STATION / LOCATION		PIPE CULVERTS CLASS D, TYPE 1 (TEMPORARY) 24" (FOOT)	36" (FOOT)	48" (FOOT)	TRENCH BACKFILL (CU. YD.)
MOT 1					
IL. RTE. 29					
STA. 76+50.00	24.89' RT	53.43			
STA. 80+75.00	23.69' RT	53.66			
TEMP 291					
1+03.00	-			106.90	
MOT 2					
IL. RTE. 29					
STA. 1429+76.93	24.84' LT	146.13			
STA. 1610+00.00	225.10' LT		49.88		
STA. 1627+35.00	84.71' LT	63.11			
STA. 1640+00.00	40.67' LT	59.60			
STA. 30+74.36	37.56' LT	140.02			
TR 74/63 CONNECTOR					
STA. 699+85.00	83.61' RT				24.99
STA. 699+85.00	311.67' LT	59.71			19.44
TOTALS		576	50	107	45

REMOVAL SCHEDULE

STATION / LOCATION			PAVEMENT REMOVAL (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, 2" (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)
IL RTE 29						
1403+00.00	TO	1418+00.00	2,494	684	472	
1418+00.00	TO	1433+00.00	7,571	1,480	34	
1433+00.00	TO	1448+00.00	4,379			
1448+00.00	TO	1463+00.00	5,277			
1568+00.00	TO	1583+00.00	744			
1583+00.00	TO	1598+00.00	4,821			
1598+00.00	TO	1613+00.00	4,555			
1613+00.00	TO	1628+00.00	4,390			
1628+00.00	TO	1643+00.00	4,396			
1643+00.00	TO	1658+00.00	4,371			
1658+00.00	TO	1665+04.46	1,907			
00+00.00	TO	08+00.00	2,480			
08+00.00	TO	23+00.00	4,374			
23+00.00	TO	38+00.00	4,377			
38+00.00	TO	53+00.00	4,367			
53+00.00	TO	68+00.00	4,777			
68+00.00	TO	83+00.00	595			
83+00.00	TO	98+00.00	4,458			
98+00.00	TO	113+00.00	7,113	1,235	163	
113+00.00	TO	128+00.00	4,215	2,077	78	
128+00.00	TO	143+00.00	2,615	994	686	
143+00.00	TO	158+00.00	1,440	427	427	
EXIST. IL RTE 29						
89+07.29	TO	183+96.28				26,816
TOTALS			85,715	6,897	1,859	26,816

REMOVAL OF EXISTING STRUCTURES

STATION / LOCATION			EXISTING SIZE / TYPE	REMOVAL OF EXISTING STRUCTURES (EACH)	LENGTH (FOOT)
IL RTE 29					
1431+61.64	58.85	LT	2' X 2' RCBC	1	45
1623+49.51	120.40	LT	2' X 2' RCBC	1	46
1656+16.18	37.64	LT	7' X 8' RCBC	1	64
1656+27.84	122.67	LT	2X60" CMP	1	120
1656+30.34	147.00	LT	RR TRESTLE	1	
7+21.88	47.46	LT	2' X 1.5' RCBC	1	45
37+15.46	46.88	LT	2' X 2' RCBC	1	46
49+70.21	40.86	LT	2' X 1.5' RCBC	1	45
60+73.30	2.01	RT	2' X 2' RCBC	1	49
81+89.79	29.76	RT	3' X 1.5' RCBC	1	44
TR 73					
180+92.54	22.09	LT	2' X 2' RCBC	1	45
EX TR 73					
296+97.12	10.87	RT	3' X 1.5' RCBC	1	21
CH23					
479+42.59	28.84	LT	6' X 8' RCBC	1	30
483+38.02	7.18	RT	84" CMP	1	83
EXISTING IL. RTE. 29					
469+98.71	0.79	LT	2' X2' RCBC	1	45
TOTAL				15	728

* REMOVAL OF CULVERTS NOT LISTED ABOVE TO BE INCLUDED IN COST OF EARTH EXCAVATION IN ACCORDANCE WITH THE GENERAL NOTES AND REMOVAL PLANS
*CONCRETE HEADWALL/SLOPEWALL REMOVAL TO BE INCLUDED IN THE COST OF REMOVAL OF EXISTING DRAINAGE STRUCTURES AND PIPE CULVERTS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

ENTRANCE, REMOVAL, STORM SEWER
TEMPORARY DRAINAGE
REMOVAL OF EXISTING STRUCTURE

SCALE: N/A DRAWN BY: K.E.U.

DATE: 03/06/2012 CHECKED BY: J.M.M.

SHT08
L:\IDOT\Q30660\draw\sheets\D672829-sht-Schedule.dgn
3/30/2012