

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	•	729	57
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
• SANGAMON AND CHRISTIAN				

GUARDRAIL SCHEDULE

STATION / LOCATION	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	TRAFFIC BARRIER, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER, TYPE 1 (SPECIAL) FLARED	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL REMOVAL
	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(FOOT)
IL RTE 29							
1655+15.00 TO 1657+15.00							200
1655+40.00 TO 1656+90.00							150
EXIST IL RTE 29							
151+35.21 TO 153+60.22	105.0	20.0	2		4	2	150
152+03.12 TO 153+90.12	67.5	20.0	1	1	4	2	100
TOTALS							
	172.5	40	3	1	8	4	600

TEMPORARY CONCRETE BARRIER & IMPACT ATTENUATOR SCHEDULE

STATION / LOCATION	TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TEST LEVEL 3	BARRIER WALL MARKERS, TYPE C
	(FOOT)	(EACH)	(EACH)
IL RTE 29			
STA. 1654+02.75 TO 1659+65.25	RT	562.5	2
			96
TOTALS			
		562.5	2
			96

BOX CULVERT SCHEDULE

STATION / LOCATION	POROUS GRANULAR EMBANKMENT	FILTER FABRIC	PRECAST CONCRETE BOX CULVERT					CONCRETE BOX CULVERTS	REINFORCEMENT BARS	REINFORCEMENT BARS, EPOXY COATED	ROCK FILL FOUNDATION	GRANULAR CULVERT BACKFILL
			4'x2'	5'x3'	10'x5'	10'x6'	12' x 7'					
			FOOT	FOOT	FOOT	FOOT	FOOT					
IL RTE 29												
1479+05.00	187	809			336		86.4	13,670		781.0	679	
1507+00.00	76	459	168				8.6	1,100		233.0	420	
1525+64.00	201	836			324		77.0	12,210		737.0	747	
1532+90.00	94	492		156			10.4	1,340		193.0	176	
1582+55.00	98	511		156			12.5	1,730		201.0	245	
1656+34.34	336	1365					273.8	67,970		601.0	378	
CH 23												
483+34.34	633	2546				390	159.7	33,200	230	936.0	45	
TR 88												
598+95.00	86	447		138			11.6	1,560		178.0	166	
TOTALS												
	1711	7465	168	450	336	324	390	640	132,780	230	3,860.0	2,856

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 GUARDRAIL
 TEMPORARY CONCRETE BARRIER & IMPACT ATTENUATOR
 BOX CULVERT

SCALE: N/A
 DATE: 03/06/2012

DRAWN BY: K.E.J.
 CHECKED BY: J.M.M.

SCHEDULE OF QUANTITIES: IL. RTE. 29