CONTRACT NO. 72829

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	*	729	322
STA. 1503+50		TO STA. 1518+50		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* SANGAMON AND CHRISTIAN

SCALE: 1" = 50'

SW 1/4 SECTION 13, T.14N., R.3W., 3RD P.M.

PARCEL NO. 6041323 & TE
WALTER C. STOKES, AS TO UNDIVIDED 1/2 INTEREST;
AND WALTER C. STOKES, A LIFE ESTATE WITH THE
REMAINDER INTEREST IN THE CHILD OR CHILDREN OF
WALTER C. STOKES, AS TO AN UNDIVIDED 1/2 INTEREST

TOTAL AREA	=	79.545	ACRES ±
AREA REQUIRED	=	8.381	ACRES ±
EXISTING R.O.W.	=	0.128	ACRES ±
TOTAL AREA REQUIRED	=	8.509	ACRES ±
TOTAL REMAINING	=	71.036	ACRES ±

REMAINING AREA THIS SIDE
37.423 AC ±

IRON PIN (FOUND)
NW COR, SW1/4, SECTION 13
T14N, R3W, 3RD P.M.

NW 1/4 SEC. 13.
T.14N., R.3W., 3RD P.M.

STA. 1515+40.47
349.92' LT.

STA. 1515+17.43, 364.32' LT.
SE CORNER, SW 1/4, NW 1/4 , SEC 13
T14N, R3W, 3RD P.M.

PARCEL NO. 6041327 A, B & PE
BARBARA L. HART,
MOLLIE CHRISTINE CARY
AND DOROTHY JEAN BRICKEY
SEE SHEET 11 FOR TABULATIONS

PROP. R.O.W. & A/C
E. LINE SW1/4, NW1/4, SEC. 13
PROPOSED CONSTRUCTION LIMITS

EXISTING R.O.W.
PROPOSED CONSTRUCTION LIMITS
PROP. R.O.W. & A/C
EXISTING R.O.W.

6041382

END A/C
STA. 1512+16.25
130.00' LT.

END A/C
STA. 1511+66.25
130.00' LT.

STA. 1513+60.20
130.00' LT.

STA. 1513+41.56
130.00' LT.

PROPOSED ℄ FAP 75 (IL. RTE. 29)

PROPOSED R.O.W. & A/C
PROPOSED CONSTRUCTION LIMITS

R = 5119.33'

S. 88° 51' 24" W
CORNER TO ℄
1755.41'

6041323

ENTRANCE
1511+91.25

MATCHLINE STA. 1503+50

J 1505+00

I 1510+00

I 1515+00

MATCHLINE STA. 1518+50

℄ STA. 1512+80.17

PROPOSED CONSTRUCTION LIMITS
PROPOSED R.O.W. & A/C

R= 5374.33'

R= 5374.33'

PROPOSED CONSTRUCTION LIMITS
PROPOSED R.O.W. & A/C

END A/C
STA. 1511+47.61
125.00' RT.

STA. 1511+47.61
164.00' RT.

STA. 1511+66.64
163.87' RT.

END A/C
STA. 1512+34.89
125.00' RT.

STA. 1512+34.89
164.00' RT.

STA. 1512+11.50
163.85' RT.

STA. 1511+85.73
163.82' RT.

PARCEL NO. 6041382
DUANE R. STOCK AND CYNTHIA A. STOCK

TOTAL AREA	=	34.156	ACRES ±
AREA REQUIRED	=	5.354	ACRES ±
EXISTING R.O.W.	=	0.344	ACRES ±
TOTAL REQUIRED	=	5.698	ACRES ±
TOTAL REMAINING	=	28.458	ACRES ±

NW 1/4 SECTION 13, T.14N., R.3W., 3RD P.M.

PARCEL NO. 6041323
WALTER C. STOKES
SEE ABOVE

REMAINING AREA THIS SIDE
33.613 AC ±

N 88° 51' 24" E 898.28'
CORNER TO ℄
EXISTING R.O.W.
℄ N. LINE, SW1/4, SEC. 13
S. LINE, NW1/4, SEC. 13
EXISTING R.O.W.

PROP. IL. RTE 29
CURVE-2 DATA
PI STA. = 1513+04.87
Δ = 57° 39' 14" (LT)
D = 1° 05' 29"
R = 5,249.33'
T = 2,889.06'
L = 5,282.14'
E = 742.51'
P.C. STA. = 1484+15.81
P.T. STA. = 1536+97.95

SW 1/4 SECTION 13, T.14N., R.3W., 3RD P.M.

IRON PIN (FOUND)
NE CORNER, SW1/4, SECTION 13
T14N, R3W, 3RD P.M.

NOTES:

BEARINGS ARE BASED ON THE ILLINOIS STATE PLANE COORDINATE SYSTEM NAD 83 (1986) WEST ZONE.

PLAN DISTANCES AND STATIONING ARE IN GRID ENGLISH. TO CONVERT TO GROUND DIVIDE BY GRID FACTOR. CONVERSION FACTOR = 0.99996337

REVISION	
DATE	DESCRIPTION

©Copyright CMT, Inc.

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
License No. 184-000613

RIGHT OF WAY PLANS

ROUTE: FAP 75 (IL ROUTE 29)
SECTION: 84-11(11B), 11-2(2B,B-1)
COUNTY: CHRISTIAN
JOB NO.: R-96-004-01
STA. 1503+50 TO STA. 1518+50
SCALE: 1" = 50'

SHEET NO. 10 OF 35

L:\DOT\030660\dr-ow\sheets\D672829-sht-ROWPLN_010.dgn
3/16/2012