CONTRACT NO. 72829

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
75	84-12; 11-3	•	729	677
STA.	100+00	TO STA. 104+00		
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		

• SANGAMON AND CHRISTIAN

SCALE 5' 10'

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TYING-IN-LINE		
NOTE BOOK	AREAS	
NO.	AREAS CHECKED	

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TYING-IN-LINE		
NOTE BOOK	AREAS	
NO.	AREAS CHECKED	

PLOT DATE : 3/16/2012
FILE NAME : ...\06728\24-sht-xsht-TR7463N.dgn
PLOT SCALE : 21.1765 ' / IN.
REFERENCE : REF

100+00.00 — STAGE-2 EXCAVATION=61.7 EMBANKMENT=43.4

101+00.00 — STAGE-2 EXCAVATION=59.8 EMBANKMENT=37.0

102+00.00 — STAGE-2 EXCAVATION=102.5 EMBANKMENT=13.4

102+70.00 — STAGE-2 EXCAVATION=32.5 EMBANKMENT=9.4

103+00.00 — STAGE-2 EXCAVATION=55.4 EMBANKMENT=4.7

103+64.27 — STAGE-2 EXCAVATION=75.6 EMBANKMENT=0.9

104+00.00 — STAGE-2 EXCAVATION=83.3 EMBANKMENT=1.4

PR ROW · EX ROW · S.D. · PROFILE F.E. LT. · PIPE CULVERT CLASS D, TYPE 1, 12" INV. = 585.83 · PIPE CULVERT CLASS D, TYPE 1, 12" INV. = 584.74 · TR 74/63 CONNECTOR PROFILE

NORTH

CROSS SECTIONS: TR 74 (625 E)/TR 63 (2300 N) NORTH – STA. 100+00 TO STA. 104+00