

SUMMARY OF QUANTITIES

CONSTRUCTION CODE
0021
90% FEDERAL
10% STATE
HIGHWAY LIGHTING
RURAL

URBAN

CODE	ITEM	UNIT	TOTAL	RURAL
67100100	MOBILIZATION	L SUM	1	1
72000100	SIGN PANEL - TYPE 1	SQ FT	25.2	25.2
72000200	SIGN PANEL - TYPE 2	SQ FT	16	16
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	52	52
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	72	72
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	401	401
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	3	3
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	1	1
83009600	LIGHT POLE, ALUMINUM, 45 FT. M. H., 15 FT. MAST ARM	EACH	3	3
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	20	20
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	3	3
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1
X0326899	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	1	1

• SPECIALTY ITEMS