

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	84-91	SANGAMON	7	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

LOCATION	CLASS A PATCHES					CLASS B PATCHES			CLASS A PATCHES			CLASS B PATCHES			SAW CUTS	TIE BARS EACH	DOWEL BARS EACH	PATCH REINF SQ YD	
	PASS.	CENT.	DRIV.	WIDTH	SQ YD	RAMP	LENGTH(FT)	WIDTH	SQ YD	11 IN	11 IN	11 IN	11 IN	11 IN					11 IN
										TY II	TY III	TY IV	TY II	TY III					TY IV
FAI 72 WEST OF WABASH																			
STA 303+90			10.0	12.0	13.3				13.3						68.0			13.3	
STA 284+95			6.0	12.0	8.0				8.0						60.0			8.0	
STA 258+00			8.0	12.0	10.7				10.7						64.0			10.7	
STA 243+00	14.0			12.0	18.7					18.7					76.0			18.7	
STA 243+00			14.0	12.0	18.7					18.7					76.0			18.7	
STA 232+70			6.0	12.0	8.0				8.0						60.0			8.0	
STA 232+10			8.0	12.0	10.7				10.7						64.0			10.7	
STA 207+65			8.0	12.0	10.7				10.7						64.0			10.7	
STA 206+10			6.0	12.0	8.0				8.0						60.0			8.0	
STA 100+60			25.0	12.0	33.3						33.3				98.0	13		33.3	
STA 31+75			6.0	12.0	8.0				8.0						60.0			8.0	
FAI 72 WEST OF WABASH																			
STA 12+50			50.0	12.0	66.7						66.7				148.0	26		66.7	
STA 16+80			10.0	12.0	13.3				13.3						68.0			13.3	
STA 84+30			10.0	12.0	13.3				13.3						68.0			13.3	
STA 176+40			10.0	12.0	13.3				13.3						68.0			13.3	
STA 178+50			6.0	12.0	8.0				8.0						60.0			8.0	
STA 183+00			6.0	12.0	8.0				8.0						60.0			8.0	
STA 184+30			15.0	12.0	20.0					20.0					78.0			20.0	
STA 206+70			10.0	12.0	13.3				13.3						68.0			13.3	
STA 207+10			12.0	12.0	16.0					16.0					72.0			16.0	
STA 282+90			6.0	12.0	8.0				8.0						60.0			8.0	
STA 382+70			6.0	12.0	8.0				8.0						60.0			8.0	
STA 383+00			6.0	12.0	8.0				8.0						60.0			8.0	
STA 395+30			6.0	12.0	8.0				8.0						60.0			8.0	
FAI 72 RAMPS NEW BERLIN																			
STA 105+80						A	10.0	16.0	17.8				17.8		68.0		28		
STA 209+00						B	8.0	16.0	14.2			14.2			64.0		28		
STA 305+75						C	8.0	16.0	14.2			14.2			64.0		28		
STA 315+00						C	6.0	16.0	10.7			10.7			60.0		28		
STA 410+00						D	6.0	16.0	10.7			10.7			60.0		28		
					352.0				67.6	178.6	73.4	100.0	49.8	17.8	0.0	1996.0	39	140.0	352.0

PLOT DATE = 04-01-2012 08:22:38AM
 FILE NAME = S:\CONTRACTS\CDV\72F47\ASCHEDULES.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = sherpac

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

FAI 72 (I 72)
SECTION (84-91)
SANGAMON COUNTY

SCALE: _____ DRAWN BY _____
DATE _____ CHECKED BY _____