

90% FED  
10% STATE

90% FED  
10% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	
X 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	212	212		
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	40	40		
80500100	SERVICE INSTALLATION, TYPE A	EACH	1		1	
81028310	UNDERGROUND CONDUIT, PVC, 3/4" DIA.	FOOT	85		85	
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	833		833	
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	36		36	
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	110		110	
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	754		754	
81400100	HANDHOLE	EACH	14		14	
81400300	DOUBLE HANDHOLE	EACH	1		1	
81500100	GULFBOX JUNCTION	EACH	4		4	
85700210	<del>RAILROAD</del> FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1	
86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	2		2	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	902		902	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5490		5490	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0005	0021	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	656		656	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4349		4349	
87301605	ELECTRIC CABLE IN CONDUIT, COMMUNICATION, NO. 16 3 PAIR	FOOT	160		160	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	20		20	
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	915		915	
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	1		1	
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	10		10	
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	3		3	
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1	
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2		2	
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1	
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	42		42	
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3.5		3.5	

X SPECIALTY ITEM

FILE NAME #	USER NAME # swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pvidot\swartzw\0273662\077	539-sht-sq.dgn	DRAWN -	REVISED -				320	(1372,139-X-2)N	MACON	39	6	
PLOT SCALE = 100.0000' / 1" =	CHECKED -	REVISOR -	REVISOR -		SCALE: N/A		SHEET 3 OF 5 SHEETS		STA.	TO STA.	ILLINOIS FED. AID PROJECT	
PLOT DATE = 4/6/2012	DATE -	REVISOR -	REVISOR -		CONTRACT NO. 74539							