Sta 188+53 73' Lt
Existing Traffic Signal Post
Foundation to be utilized for
Proposed Signal Post

The existing signal post will be
taken out of service at the
time of construction.

Sta 186+23
49' Rt

144'-1 1/2"
PVC

Sta 187+67
58' Rt

Sta 188+15
6' Lt
Conc Fdn Ty A
14' Post

Sta 188+30
6' Lt

141'-1 1/2"
PVC

Sta 188+74
3' Lt
Conc Fdn Ty A
14' Post

Sta 189+01
61' Rt
Conc Fdn Ty A
14' Post

12'-1 1/2"
PVC

Sta 189+04
72' Rt

Sta 189+33
62' Rt
Conc Fdn Ty A
12' Post

62'-3"
PVC

Sta 188+31
67' Lt
Conc Fdn Ty E
36" Dia, 18' Lg
46' M.A.

15'-1 1/2"
PVC

Sta 188+43
80' Lt

Sta 188+53
73' Lt
Conc Fdn Ty A
16' Post

Sta 8+97.5
21' Rt

103'-4"
PVC

11.6 11.5
46' M.A.

10'-1 1/2"
PVC

48'-4"
PVC

71'-4"
PVC

13'-1 1/2"
PVC

42'-1 1/2"
PVC

100' R

+84

+00

Sta 9+02
18' Rt
Conc Fdn Ty A
14' Post

5'-1 1/2"
PVC

31'-1 1/2"
PVC

+00

+00

Sta 189+99
59' Rt
Conc Fdn Ty A
16' Post

41'-4"
PVC

3'-1 1/2"
PVC

+54

Sta 10+64
23' Rt

30' M.A.

12'

4'-1 1/2"
PVC

Sta 10+70
24' Rt
Conc Fdn Ty E
30" Dia, 12' Lg
30' M.A.

Sta 190+03
62' Rt

34'-1 1/2"
PVC

53'-4"
PVC

Sta 190+55
62' Lt
Conc Fdn Ty E
36" Dia, 11' Lg
38' M.A.

4'-1 1/2"
PVC

Sta 190+60
67' Rt

61'-4"
PVC

38' M.A.

12'

12'

Sta 190+16
3' Rt
Conc Fdn Ty A
14' Post

+02

99'-4"
PVC

100' R

Sta 190+52
3' Rt

13'-1 1/2"
PVC

Sta 190+67
3' Rt
Conc Fdn Ty A
14' Post

Sta 8+84
48' Lt

Sta 8+92
48' Lt
Conc Fdn Ty E
36" Dia, 13' Lg
48' M.A.

12'

7'-1 1/2"
PVC
48' M.A.

18'-1 1/2"
PVC

8'-4"
PVC

Sta 189+82
62' Lt
Conc Fdn Ty A
16' Post

+88

Sta 189+87
76' Lt

131'-1 1/2"
PVC

Sta 191+18
67' Lt

240' DECEL LANE

144'-1 1/2"
PVC

Sta 192+63
66' Lt

11'

COUNTRY CLUB ROAD

US 36/ILL 121

Existing 2" G.S. Conduit
to Railroad Cabinet

36'-2"
PVC
(Connect to
Ex 2" G.S. Conduit)

38'-3"
PVC

Sta 189+77
86' Lt

10'-3"
PVC

Service
Installation,
Ty A

2@4'-4"
PVC

Sta 189+77
79' Lt

N

FILE NAME = c:\pw_work\pwidot\mcclellanla\d0273662\D774539-sht-ts-1.dgn	USER NAME = mcclellanla	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/12/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNAL LAYOUT
INTERSECTION US 36 & COUNTRY CLUB ROAD

SCALE: 20 | SHEET 4 OF 12 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	(137Z,139-X-2)N	MACON	39	26
		CONTRACT NO. 74539		
		ILLINOIS FED. AID PROJECT		