

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES, SUMMARY OF QUANTITIES
3	SCHEDULES OF QUANTITIES
4	LOCATION MAP
5-8	PAVEMENT MARKING DETAILS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 8.

STANDARD 701001-02
 STANDARD 701006-03
 STANDARD 701011-02
 STANDARD 701301-04
 STANDARD 701306-03
 STANDARD 701901-02

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS; THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2012; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THIS PROPOSAL.

THE PROPOSED WORK IS LOCATED ON CADWELL ROAD FROM ILLINOIS ROUTE 121 NORTH TO ILLINOIS ROUTE 133 IN MOULTRIE COUNTY. IT IS THE INTENT OF THE DEPARTMENT THAT THE SURFACE TREATMENT EXTEND 6" ONTO THE SHOULDERS TO HELP SEAL THE CONSTRUCTION JOINT BETWEEN THE PAVEMENT AND SHOULDERS.

THE WORK IN THIS SECTION CONSISTS OF CONSTRUCTION OF SEAL COAT FOR BITUMINOUS SURFACE TREATMENT CLASS A-1, PAVEMENT MARKING, AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION PER THE PLANS AND STANDARD SPECIFICATIONS.

THE MATERIAL USED FOR SEAL COAT AGGREGATE SHALL BE CA-16 CRUSHED STONE.

TEMPORARY PAINT PAVEMENT MARKING LINE - 4" SHALL BE APPLIED TO THE AREAS WHICH HAVE BEEN COVERED WITH BITUMINOUS SURFACE TREATMENT AT THE END OF EACH WORK DAY. THE SHORT TERM PAVEMENT MARKING SHALL BE PAINT. THE SHORT TERM PAVEMENT MARKING SHALL BE SPACED SO THAT IT WILL BE COVERED BY THE PAINT PAVEMENT MARKING - LINE 4".

RAISED REFLECTIVE PAVEMENT MARKERS AND SURVEY MONUMENT VAULTS SHALL BE KEPT FREE OF THE SEAL COAT. THEY SHALL BE PROTECTED BY COVERING THEM WITH TAPE. THE COST TO COVER THE RAISED REFLECTIVE PAVEMENT MARKERS AND SURVEY MONUMENT VAULTS WILL BE INCLUDED IN THE COST OF THE BITUMINOUS MATERIALS (COVER AND SEAL COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED. REMOVING THE TAPE AFTER COMPLETING THE SEAL COAT IS ALSO INCLUDED IN THE COST OF THE BITUMINOUS MATERIALS (COVER AND SEAL COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

100% STATE

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				0005		
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	41642	41642		
40300600	SEAL COAT AGGREGATE	TON	1487	1487		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4256	4256		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	355	355		
X 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	114	114		
X 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1974	1974		
X 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	271	271		
X 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	141	141		
X 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	104116	104116		

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -
c:\pwork\p101\swartzw\d0285365\077	558-shr-index.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**INDEX OF SHEETS, GENERAL NOTES
AND SUMMARY OF QUANTITIES**

SCALE: NA SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
659	D7 SEAL COAT 2013-1	MOULTRIE	8	2
			CONTRACT NO. 74558	
ILLINOIS FED. AID PROJECT				