

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	L23EL	L23EU		L23EL	L23E	L23EU		
				ACF	ACM	ACM	ACF	ACF	ACM		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY		
				ROADWAY 0001 URBAN F.A.P. 809	ROADWAY 0001 URBAN F.A.U. 9251	ROADWAY 0001 URBAN F.A.U. 9269	BOX CULVERT SN 082-0400 0040 URBAN	HIGHWAY LIGHTING 0021 URBAN	BICYCLE/PEDS 0028 URBAN FAU		
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	11	9		2					
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	7	5	1	1					
72900200	METAL POST - TYPE B	FOOT	860	757	45	58					
x 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	267	173.4	62.4	31.2					
x 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	7622	5433	768	1421					
x 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	379	379							
x 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	1167	1042	51	74					
x 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	16	6	10						
x 78200300	PRISMATIC CURB REFLECTOR	EACH	295	216	35	44					
x 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	12							
x 78200530	BARRIER WALL MARKERS, TYPE C	EACH	10	10							
x 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3222	2432	255	535					
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1				1				

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -
ci:\pw_work\pvsidot\owenbj\d0133899\p1n10025a.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -
PLOT DATE = 3/23/2012		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 10 OF 15 SHEETS STA. TO STA.

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269			
F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS
①	135-N	ST. CLAIR	206
			12
			CONTRACT NO. 76D06
ILLINOIS FED. AID PROJECT			