

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	L23EL	L23EU		L23EL	L23E	L23EU
				ACF	ACM	ACM	ACF	ACF	ACM
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY
				ROADWAY 0001	ROADWAY 0001	ROADWAY 0001	BOX CULVERT SN 082-0400	FAP HIGHWAY LIGHTING	BICYCLE/PEDS 0028
URBAN F.A.P. 809	URBAN F.A.U. 9251	URBAN F.A.U. 9269	0040 URBAN	0021 URBAN	URBAN FAU				
81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	545					545	
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	200					200	
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 12" X 6"	EACH	8					8	
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	38					38	
82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	4					4	
82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1					1	
83009400	LIGHT POLE, ALUMINUM, 45 FT. M.H., 10 FT. MAST ARM	EACH	38					38	
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	247					247	
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	38					38	
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	3					3	
84200804	REMOVAL OF POLE FOUNDATION	EACH	3					3	
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1					1	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1					1	
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1					1	

FILE NAME =	USER NAME = owerbj	DESIGNED -	REVISED -
ce:\pwwork\pwwork\overbj\d0133099\p110005a.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/23/2012	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET 11 OF 15 SHEETS STA. TO STA.

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	135-N	ST. CLAIR	206	13
			CONTRACT NO. 76D06	
ILLINOIS FED. AID PROJECT				