EARTHWORK

STAGE	LOCATION	STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
			CU YD	CU YD	CU YD	CU YD
A1	IL 158	50+50.00 TO 51+75.00	25	20	32	-12
A2	IL 158	50+50.00 TO 51+75.00	51	38	1	37
A3	IL 158	50+50.00 TO 51+75.00	30	23	11	12
B1	IL 158	0+00.00 TO 4+00.00	237	179	912	-733
		0+00.00 TO 53+69.94	184	138	214	-76
	WHISKEY ROAD	60+50.00 TO 61+94.66	43	33	150	-117
	IL 15 EB ENTRANCE RAMP	0+00.00 TO 71+59.71	78	59	169	-110
	IL 15 EB EXIT RAMP	80+50.00 TO 0+00.00	87	66	44	22
B2	IL 158	0+00.00 TO 2+50.00	115	87	278	-191
B3	IL 158	0+00.00 TO 2+50.00	67	51	181	-130
C1	CENTREVILLE AVENUE	31+50.00 TO 34+71.81	119	90	21	69
	TEMPORARY IL 158	1+00.00 TO 5+00.00	1170	880	1108	-228
C2	IL 158	2+50.00 TO 5+00.00	86	64	1346	-1282
	CENTREVILLE AVENUE	30+00.00 TO 31+00.00	396	297	861	-564
	IL 15 WB EXIT RAMP	10+50.00 TO 12+60.00	157	118	1317	-1199
	IL 13 / 158	20+50.00 TO 24+05.55	1133	851	153	698
	IL 13	41+00.00 TO 41+50.00	89	67	4	63
	IL 15 WB ENTRANCE RAMP	90+50.00 TO 91+00.00	0	0	293	-293
C3	CENTREVILLE AVENUE	31+00.00 TO 32+00.00	14	10	304	-294
	IL 13 / 158	21+00.00 TO 24+05.55	344	260	71	189
C4	IL 158	2+50.00 TO 3+50.00	27	21	68	-47
C5	IL 13	41+50.00 TO 44+08.08	384	290	19	271
	IL 15 WB ENTRANCE RAMP	91+00.00 TO 97+23.38	1060	796	1120	-324
	IL 15 WB ENTRANCE BYPASS	101+50.00 TO 103+68.66	334	252	709	-457
		TOTAL	6230	4690	9386	-4696
		EARTH EXCAVATION	6230	FURNISHED EXCAVATION		4695

PAVEMENT REMOVAL

LOCATION	STATION	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 2-1/4"	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	GUTTER REMOVAL	MEDIAN REMOVAL	PAVED DITCH REMOVAL	PAVED SHOULDER REMOVAL
		SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ FT	FOOT	SQ YD
IL 158	0+00.00 TO 5+37.77 -	2092			549	244	102		218
	50+00.00 TO 51+75.00 -	650			281		16		
	51+75.00 TO 53+00.00		502						
	52+24.94 LT			71					
	52+49.66 RT			128					
	52+97.78 LT			89					
CENTREVILLE AVENUE	30+00.00 TO 31+71.69 -	779			565				
	31+66.98 TO 34+71.81		1188						
	32+30.05 RT			83					
	33+36.18 RT			70					
IL 15 WB EXIT RAMP	10+14.55 TO 12+60.00 -	548			143			174	210
IL 13 / IL 158	20+12.85 TO 22+87.50 -	1311			499				
	22+00.00 LT			152					
	22+87.50 TO 24+05.55		353						
IL 13	40+35.19 TO 41+61.10 -	702			578				
	41+61.10 TO 44+08.08		947						
	41+62.00 LT			1868					
	42+04.13 RT			78					
	43+09.69 RT			61					
	43+86.10 RT			77					
TEMPORARY WHISKEY ROAD	60+37.99 TO 61+06.47 -	113							
WHISKEY RD	60+42.45 TO 61+94.49 -	447							
IL 15 EB ENTRANCE	70+00.24 TO 71+60.07 -	449			237			46	16
IL 15 EB EXIT RAMP	80+08.93 TO 81+60.00 -	448			155			15	64
IL 15 WB ENTRANCE	90+00.00 TO 81+05.91 -	832			239			661	630
TEMPORARY RUNAROUND	0+97.75 TO 5+14.85 -	1539							
	TOTAL	9910	2990	2677	3246	244	118	896	1138

PAVEMENT MARKING REMOVAL

LOCATION	STATION	SIDE	PAVEMENT MARKING REMOVAL
			SQ FT
IL 158	0+06.80 TO 5+37.77	LT	134
0.00	0+52.00 TO 5+37.77	-	300
0.00	0+61.27 TO 5+37.77	RT	132
0.00	0+00.00 0.00 0+61.27	LT	24
0.00	0+00.00 0.00 0+83.00	-	24
0.00	0+00.00 0.00 3+55.00	-	24
0.00	0+00.00 0.00 3+75.00	RT	24
0.00	0+00.00 0.00 4+40.00	LT	50
0.00	0+00.00 0.00 50+30.00	RT	24
0.00	50+73.46 TO 720+37.84	RT	217
0.00	50+51.08 TO 720+37.84	LT	225
0.00	50+32.02 TO 51+14.50	RT	54
0.00	50+32.02 TO 51+14.50	-	60
0.00	50+32.02 TO 51+14.50	LT	54
0.00	0+00.00 0.00 50+32.02	RT	24
0.00	51+14.50 TO 720+37.84	RT	255
0.00	51+14.50 TO 720+37.84	-	54
0.00	51+14.50 TO 720+37.84	LT	255
CENTREVILLE AVENUE	0+00.00 0.00 31+45.00	LT	70
0.00	31+45.00 TO 34+71.81	-	218
0.00	31+45.00 TO 32+60.00	LT	38
0.00	31+45.00 TO 34+71.81	RT	109
0.00	0+00.00 0.00 31+65.00	LT	30
0.00	0+00.00 0.00 32+40.00	LT	30
0.00	33+50.32 TO 34+71.81	LT	40
IL 13 / 158	0+00.00 0.00 20+87.50	-	60
0.00	20+87.50 TO 24+05.55	-	167
0.00	20+87.50 TO 24+05.55	LT	93
0.00	20+87.50 TO 24+05.55	LT	52
0.00	0+00.00 0.00 21+32.50	LT	9
0.00	0+00.00 0.00 22+07.50	LT	9
0.00	20+89.50 TO 24+05.55	RT	93
0.00	22+45.00 TO 24+05.55	-	15
IL 13	0+00.00 0.00 41+17.50	RT	10
0.00	41+17.50 TO 42+86.84	LT	57
0.00	41+17.50 TO 42+86.84	-	113
0.00	41+17.50 TO 42+86.84	RT	57
0.00	0+00.00 0.00 41+35.00	RT	9
0.00	0+00.00 0.00 41+90.00	RT	9
		TOTAL	3222

SIGN REMOVAL

LOCATION	STATION	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B
		EACH	EACH
IL 158	53+49.00 28.00 LT	1	
	0+61.00 30.00 RT		1
	1+35.50 23.50 LT		1
	3+50.00 43.00 LT		1
	3+94.00 23.00 RT		1
	4+80.00 31.35 LT	1	
CENTREVILLE AVENUE	30+27.50 28.50 RT		1
	30+40.50 25.50 RT	1	
	31+60.00 33.00 LT	1	
IL 15 WB EXIT RAMP	10+50.00 68.00 RT	1	
	10+81.00 28.50 RT	1	
	11+04.00 58.50 RT	1	
IL 13 / 158	21+22.00 81.50 LT	1	
	21+45.00 62.50 LT		1
IL 13	41+04.00 15.75 RT		1
IL 15 EB EXIT RAMP	80+24.00 25.00 LT	1	
	80+64.00 8.50 RT	1	
	80+75.00 30.50 LT	1	
	TOTAL	11	7

CONCRETE SLAB REMOVAL

LOCATION	STATION	OFFSET	CONCRETE SLAB REMOVAL
			SQ YD
IL 13	41+20	0+29.00 LT	31
	41+39	0+50.00 LT	55
		TOTAL	86

① F.A.P. RTE 809 / F.A.U. RTE 9251 / F.A.U. RTE 9269

LAST SAVED = 3/20/2012
PEN TABLE = V8-Half.tbl
PLOT DRIVER = TR-V8pdf-Black-Half.plt

FILE NAME = ::\0906600\0906603\cad\t_plans\005-D876D06-Sht-Schedule.dgn
USER NAME = beriechmann
PLOT SCALE = 40.0000 ' / IN.
PLOT DATE = 3/20/2012 4:10:04 PM
DESIGNED -
DRAWN -
CHECKED -
DATE -
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HORNER & SHIFRIN, INC. ENGINEERS
SCALE: NONE

SCHEDULE OF QUANTITIES
EARTHWORK, PAVEMENT MARKING REMOVAL, PAVEMENT REMOVAL, SIGN REMOVAL, CONCRETE SLAB REMOVAL

SHEET NO. 1 OF 8 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	135-N	ST. CLAIR	206	24

CONTRACT NO. 76D06
ILLINOIS FED. AID PROJECT