

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE 0005		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	47	47		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32.2	32.2		
40600300	AGGREGATE (PRIME COAT)	TON	53	53		
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	734	734		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	415	415		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	56	56		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1467	1467		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.9	0.9		
40800030	AGGREGATE (PRIME COAT)	TON	2	2		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	24	24		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	21198	21198		
44004250	PAVED SHOULDER REMOVAL	SQ YD	777	777		

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FEDERAL 20% STATE 0005		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	77	77		
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	20	20		
44200184	PAVEMENT PATCHING, TYPE III, 15 INCH	SQ YD	269	269		
44200186	PAVEMENT PATCHING, TYPE IV, 15 INCH	SQ YD	157	157		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6194	6194		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	107	107		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2071	2071		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	469	469		
X 63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	3912.5	3912.5		
X 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4		
X 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
63200310	GUARDRAIL REMOVAL	FOOT	4382	4382		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5		

X SPECIALTY ITEM

FILE NAME =	USER NAME = muhlfeldec	DESIGNED - ACM	REVISED -
as:\pw\work\pvidot\muhlfeldec\d0254746\0876E87-sht-500.dgn		DRAWN - ACM	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/23/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET 1 OF 2 SHEETS STA. TO STA.

F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
674	3IRS-3	ST. CLAIR	12	3
CONTRACT NO. 76E87				
ILLINOIS FED. AID PROJECT				