

RESURFACING SCHEDULE														
LOCATION			HMA SURFACE REMOVAL 1"	HMA SURFACE REMOVAL BUTT JOINT	STRIP REFL. CRACK CONTROL TREATMENT	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED LEVELING BINDER (MACHINE METHOD) N50	POLYMERIZED HMA. SURFACE CSE. MIX. D N90	EXCAVATION AND GRADING EX. SHOULDERS	PAVED SHOULDER REMOVAL	HMA SHOULDERS 8 INCH	HMA SHOULDERS	AGGREGATE SHOULDERS TYPE B
STATION	TO	STATION	SQ YD	SQ YD	FEET	TON	TON	TON	TON	UNITS	SQ YD	SQ YD	TON	TON
125+65.60	TO	137+00.00	3025.07	66.7	2268.8	4.73	7.56	127.05	254.11	22.69	378.13	1008.36		18.38
137+00.00	TO	152+00.00	4031.48		3000	6.63	10.59	168.00	336.00	23.89	398.13	1061.67	29.91	24.30
152+00.00	TO	162+63.94	3782.90	88.9	91.02	5.92	9.46	119.16	238.32				119.16	17.24
162+63.94	TO	168+57.61	2110.83	88.9		3.30	5.28	66.49	132.98				66.49	9.62
168+57.61	TO	182+00.00	4772.94			7.47	11.93	150.35	300.70				150.35	21.75
182+00.00	TO	191+12.80	3245.51	88.9	833.64	5.08	8.11	102.23	204.47				102.23	14.79
TOTAL			20968.73	333.4	6193.46	33.13	52.94	733.29	1466.57	46.58	776.26	2070.03	468.14	106.08
ROUNDED			20969	334	6194	33.2	53	734	1467	47	777	2071	469	107

THIS IS NOT A TOTAL QUANTITY, SEE ENTRANCE AND SIDE ROAD SCHEDULE

GUARDRAIL SCHEDULE											
LOCATION			SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
STATION	TO	STATION	RT/LT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
157+42.05	TO	163+47.97	LT	606.25	512.5	1	1	8			1
+4.00	TO	163+88.11	RT	568.75	475.0	1	1	7			1
163+47.97	TO	167+35.22	LT						6	6	
163+88.11	TO	167+72.44	RT						6	6	
167+35.22	TO	177+26.33	LT	1093.75	1000.0	1	1	17			1
167+72.44	TO	175+68.74	RT	793.75	700.0	1	1	10			1
177+26.33	TO	189+53.99	LT	1318.75	1225.0	2		20			2
TOTAL				4381.25	3912.5	6	4	62	12	12	6
ROUNDED				4382	3912.5	6	4	62	12	12	6

PAVEMENT MARKING SCHEDULE																	
LOCATION			THERMOPLASTIC 4 INCH WHITE SOLID LINE	THERMOPLASTIC 4 INCH YELLOW SOLID LINE	THERMOPLASTIC 4 INCH YELLOW (SKIP DASH)	PAV. MARK. REMOVAL	POLYUREA 4 INCH WHITE SOLID LINE	POLYUREA 4 INCH YELLOW SOLID LINE	POLYUREA 4 INCH YELLOW (SKIP DASH)	TEMPORARY 4 INCH WHITE SOLID LINE	TEMPORARY 4 INCH YELLOW SOLID LINE	TEMPORARY 4 INCH YELLOW (SKIP DASH)	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING	AMBER RAISED REFLECTIVE PAVEMENT MARKER	AMBER RAISED REFLECTIVE PAVEMENT MARKER. BRIDGE	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
STATION	TO	STATION	FEET	FEET	FEET	SO. FEET	FEET	FEET	FEET	FEET	FEET	FEET	FEET	SO. FEET	EACH	EACH	EACH
125+65.60	TO	137+00.00	2268.80	482.40	290.00					2268.80	482.40	290.00	312.00	1048.40	15		15
137+00.00	TO	152+00.00	3000.00		380.00					3000.00			492.00	1181.33	19		19
152+00.00	TO	162+63.94	2127.88	635.94	270.00					2127.88	635.94	270.00	564.00	1073.94	14		14
162+63.94	TO	167+00.00				472.40	872.12	436.06	110.00	872.12	436.06	110.00	240.00	499.39		6	6
167+00.00	TO	168+57.61				170.74	315.22	157.61	40.00	315.22	157.61	40.00	96.00	181.61		2	2
168+57.61	TO	182+00.00	2684.78	988.39	340.00					2684.78	988.39	340.00	708.00	1416.39	17		17
182+00.00	TO	191+12.81	1825.62	738.81	230.00					1825.62	738.81	230.00	492.00	986.14	12		12
SUBTOTAL			11907.08	2845.54	1510.00	643.14	1187.34	593.67	150.00	13094.42	3439.21	1660.00	2904.00	6387.21	77	8	85
TOTAL			16262.62			643.14	1931.01			18193.63			2904.00	6387.21	77	8	85
ROUNDED			16263			644	1932			18194			2904	6388	77	8	85