

PAVEMENT MARKING SCHEDULE

STATION	LENGTH	8" WHITE SOLID	4" WHITE SKIP DASH 10'-30'	4" YELLOW SOLID	4" WHITE SOLID	RRPM	RRPM REMOVAL	SHORT TERM PAVEMENT MARKING	TEMP PAVEMENT MARKING 4"	TEMP PAVEMENT MARKING 8"	WORK ZONE PAVE. MARK REMOVAL
RT (NB)		FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT	SO. FOOT
1874+15.00 TO 1886+04.77	1190	0	297	1190	1190	30	30	203	2677	0	960
1887+74.10 TO 1904+53.30	1679	0	420	1679	1679	42	42	287	3778	0	1355
1905+94.33 TO 1915+93.22	999	0	250	999	999	24	24	171	2248	0	806
1917+60.71 TO 1921+00.00	339	0	85	339	0	8	8	44	424	0	156
1921+00.00 TO 1922+50.00	150	150	38	150	0	10	10	20	188	150	169
1922+50.00 TO 1934+50.00	1200	0	300	1200	1200	30	30	205	2700	0	968
1934+50.00 TO 1941+00.00	650	0	163	650	0	16	16	85	813	0	299
1941+00.00 TO 2007+34.30	6634	0	1659	6634	6634	166	166	1134	14927	0	5354
2020+18.00 TO 2092+69.62	7252	0	1813	7252	7252	182	182	1239	16316	0	5852
2094+95.50 TO 2437+19.69	34224	0	8556	34224	34224	856	856	5849	77004	0	27618
2437+19.59 TO 2486+20.00	4900	0	1225	4900	4900	122	122	838	11026	0	3954
2486+20.00 TO 2491+57.31	537	0	134	537	0	14	14	70	672	0	247
2490+44.72 TO 2492+00.00	155	155	39	155	0	10	10	20	194	155	175
2492+00.00 TO 2515+00.00	2300	0	575	2300	2300	58	58	393	5175	0	1856
2515+00.00 TO 2524+75.00	975	0	244	975	0	24	24	128	1219	0	449
2524+75.00 TO 2654+81.28	13006	0	3252	13006	13006	326	326	2223	29264	0	10496
2656+41.78 TO 2753+09.11	9667	0	2417	9667	9667	242	242	1652	21751	0	7801
2754+89.11 TO 2862+79.00	10790	0	2697	10790	10790	270	270	1844	24277	0	8707
LT (SB)											
1874+15.00 TO 1886+04.77	1190	0	297	1190	1190	30	30	203	2677	0	960
1887+74.10 TO 1904+53.30	1679	0	420	1679	1679	42	42	287	3778	0	1355
1905+94.33 TO 1915+93.22	999	0	250	999	999	24	24	171	2248	0	806
1917+60.71 TO 1921+50.00	389	0	97	389	0	10	10	51	487	0	179
1921+50.00 TO 1932+50.00	1100	0	275	1100	1100	28	28	188	2475	0	888
1932+50.00 TO 1934+20.00	170	170	43	170	0	10	10	22	213	170	192
1934+20.00 TO 1939+62.53	543	0	136	543	0	26	26	71	678	0	250
1939+62.53 TO 2007+34.30	6772	0	1693	6772	6772	170	170	1157	15236	0	5465
2020+18.00 TO 2092+69.62	7252	0	1813	7252	7252	182	182	1239	16316	0	5852
2094+95.50 TO 2479+20.00	38425	0	9606	38425	38425	960	960	6567	86455	0	31007
2479+20.00 TO 2489+00.00	980	0	245	980	0	24	24	128	1225	0	451
2489+00.00 TO 2512+00.00	2300	0	575	2300	2300	58	58	393	5175	0	1856
2512+00.00 TO 2513+50.00	150	150	38	150	0	10	10	20	188	150	169
2513+50.00 TO 2518+75.00	525	0	131	525	0	14	14	69	656	0	242
2518+75.00 TO 2655+30.50	13656	0	3414	13656	13656	342	342	2334	30725	0	11020
2656+91.00 TO 2752+74.89	9584	0	2396	9584	9584	240	240	1638	21564	0	7734
2754+54.89 TO 2862+79.00	10824	0	2706	10824	10824	270	270	1850	24354	0	8735
TOTALS		625	48296	193185	187621	4870	4870	32794	429102	625	154382
				380806							

△ REVISED SHEET 6-1-2012

FILE NAME =	USER NAME = chids1	DESIGNED - GEL	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PAVEMENT MARKING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pwork\pwork\chids1\08301187\0876190-	t-plan.dgn	DRAWN - LAC	REVISED -			57	61-233-1,4,5,5-1,61 RS-2	MARION	8	6
PLOT SCALE = 100:1218 / in.	CHECKED - MDP	REVISED -	REVISED -			CONTRACT NO. 76F90				
PLOT DATE = 4/30/2012	DATE - 3/20/2012	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT				
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.						