

SUMMARY OF QUANTITIES

LOCATION	RURAL-STP
ROUTE	FAP 869 (IL 34)
FUNDING	80% FED 20% STATE
COUNTY	SALINE
CONSTRUCTION TYPE	ROADWAY
TYPE CODE	0004

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
40600300	AGGREGATE (PRIME COAT)	TON	23	23
40600982	HOT*MIX ASPHALT SURFACE REMOVAL • BUTT JOINT	SQ YD	31	31
40603245	POLYMERIZED HOT*MIX ASPHALT BINDER COURSE, IL=19.0, N105	TON	1,971	1,971
40603550	POLYMERIZED HOT*MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1,314	1,314
40701996	HOT*MIX ASPHALT PAVEMENT (FULL*DEPTH), 15 3/4"	SQ YD	SEE TABLE, SHEET 8	SEE TABLE, SHEET 8
40800050	INCIDENTAL HOT*MIX ASPHALT SURFACING	TON	21	21
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	SEE TABLE, SHEET 8	SEE TABLE, SHEET 8
44000100	PAVEMENT REMOVAL	SQ YD	28,782	28,782
44201789	CLASS D PATCHES, TYPE II, 12"	SQ YD	146	146
44201794	CLASS D PATCHES, TYPE III, 12"	SQ YD	17	17
44201796	CLASS D PATCHES, TYPE IV, 12"	SQ YD	26	26
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10,058	10,058