

ALTERNATE B IL 34 PAVEMENT REPLACEMENT SCHEDULE ALTERNATE PCC

LOCATION STATION TO STATION	LENGTH	ROADWAY WIDTH		ROADWAY AREA		PAVEMENT REMOVAL	PROCESSING MODIFIED SOIL 16"	LIME AT 5%	PCC PAVEMENT	STABILIZED SUBBASE	AGG. WEDGE SHOULDER, TYPE B
	EXISTING (FOR INFORMATIONAL PURPOSES ONLY)										
	FT	FT		SQ YD		SQ YD	SQ YD	TON	SQ YD	SQ YD	TON
		EXISTING	PROPOSED	EXISTING	PROPOSED						
1483+00.0 TO 1541+73.3	5873.28	27	28	17620	18272	17620	18925	596	18272	18272	446
OMISSION STR 083-0037 STA 1541+73.28 TO STA 1542+26.72											
1542+26.7 TO 1560+92.4	1865.68	27	28	5597	5804	5597	6012	189	5804	5804	142
OMISSION STR 083-0038 STA 1560+92.4 TO STA 1562+47.6											
1562+47.6 TO 1573+62.1	1114.5	27	28	3344	3467	3344	3591	113	3467	3467	85
OMISSION STR 083-0039 STA 1573+62.1 TO STA 1574+37.9											
1574+37.9 TO 1581+78.5	740.61	27	28	2222	2304	2222	2386	75	2304	2304	56
PAVEMENT REPLACEMENT TOTALS	9594					28782	30914	974	29848	29848	728
	1.82	MILES									