

SEEDING SCHEDULE

LOCATION STATION TO STATION			LENGTH	WIDTH (2 SIDES)	SEEDING AREA	NITROGEN FERTILIZER	PHOSPHORUS FERTILIZER	POTASSIUM FERTILIZER	AGRICULTURAL GROUND LIMESTONE	SEEDING, CLASS 2	MULCH, METHOD 2	
			(FOR INFORMATION ONLY)									
			FT	FT	ACRES	POUNDS	POUNDS	POUNDS	TONS	ACRE	ACRE	
1483+00.0	TO	1541+73.3	5873.28	20	2.70	243	243	243	5	2.70	2.70	
OMISSION STR 083-0037 STA 1541+73.28 TO STA 1542+26.72												
1542+26.7	TO	1560+92.4	1865.68	20	0.86	77	77	77	2	0.86	0.86	
OMISSION STR 083-0038 STA 1560+92.4 TO STA 1562+47.6												
1562+47.6	TO	1573+62.1	1114.5	20	0.51	46	46	46	1	0.51	0.51	
OMISSION STR 083-0039 STA 1573+62.1 TO STA 1574+37.9												
1574+37.9	TO	1581+78.5	740.61	20	0.34	31	31	31	1	0.34	0.34	
SEEDING TOTALS			9594			396	396	396	9	4.40	4.40	
			1.82	MILES								

PAVEMENT MARKING SCHEDULE

STATION TO STATION	PAINT PAVEMENT MARKING		TEMPORARY	SHORT-TERM	NOTES			
	4 INCH WHITE (EDGE LINE)	4 INCH (SKIP-DASH)	4 INCH	4 INCH				
	FOOT	FOOT	FOOT	FOOT				
MAINLINE: STA 1480+92 TO STA 1633+10.72								
	1483+00.0	TO	1633+10.7	30,021	3,753	33,774	3,002	
TOTAL				30,021	3,753	33,774	3,002	