

SUMMARY OF QUANTITIES

LOCATION	RURAL-STP
ROUTE	FAP 776 (IL 142)
FUNDING	100% STATE
COUNTY	SALINE
CONSTRUCTION TYPE	ROADWAY
TYPE CODE	0004

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
40600300	AGGREGATE (PRIME COAT)	TON	1	1
40600990	TEMPORARY RAMP	SQ YD	29	29
40603525	POLYMERIZED HOT•MIX ASPHALT SURFACE COURSE, MIX "C", N105	TON	34	34
40701941	HOT•MIX ASPHALT PAVEMENT (FULL•DEPTH), 13"	SQ YD	3,568	3,568
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	259	259
44000100	PAVEMENT REMOVAL	SQ YD	3,827	3,827
44000155	HOT•MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	402	402
48100100	AGGREGATE SHOULDERS, TYPE A	TON	508	508
48203045	HOT•MIX ASPHALT SHOULDERS, 12"	SQ YD	593	593
67100100	MOBILIZATION	L SUM	1	1
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -
c:\pwork\p1dot\lavenderba\0290964\78291-sht-pla.rdg	78291-sht-pla.rdg	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -
PLOT DATE = 4/5/2012		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
776	125R-1	SALINE	16	6
CONTRACT NO. 78291				
ILLINOIS FED. AID PROJECT				