

## REMOVAL SCHEDULE

LOCATION STATION TO STATION	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	REMARKS
<b>IL 13</b>	SQ YD	SQ YD	FOOT	
1819+32.35 TO 1820+67.89	241			
1820+67.89 TO 1825+00	768	193		
1825+00 TO 1830+10.98	804	227		
POSSIBLE CURB AND GUTTER			100	REMOVAL AND REPLACEMENT TO BE USED AS DIRECTED BY THE ENGINEER
<b>SUBTOTALS</b>	1813	420	100	

## PAVEMENT AND SHOULDER SCHEDULE

LOCATION STATION TO STATION	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B	STABILIZED SUB-BASE 4"	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	REMARKS
<b>IL 13</b>	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	FOOT	
1819+32.35 TO 1820+67.89	241			241	241			
1820+67.89 TO 1825+00	936	18	129	840	768	144		
1825+00 TO 1830+10.98	1004	21	153	890	804	171		
POSSIBLE CURB AND GUTTER							100	REMOVAL AND REPLACEMENT TO BE USED AS DIRECTED BY ENGINEER
<b>SUBTOTALS</b>	2181	39	282	1971	1813	315	100	

## PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PAINT PAVEMENT MARKING - LINE 4"		REMARKS
	WHITE SOLID	YELLOW SOLID	
<b>IL 13</b>	FOOT	FOOT	
1819+50 TO 1830+11		1061	INSIDE EOP
1820+68 TO 1830+11	943		OUTSIDE EOP
TOTALS	943	1061	
	2004		