

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	LOCATION #1 JACKSON CO. RURAL 100% STATE	LOCATION #2 JACKSON CO. RURAL 100% STATE
	CONSTRUCTION TYPE CODE			0005	0005
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	2,550	2,550	
40600100	BITUMINOUS MATERIALS PRIME COAT	GAL	1,691	230	1,461
40600300	AGGREGATE PRIME COAT	TON	28	4	24
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	2		2
40600982	HOT-MIX ASPHAL SURFACE REMOVAL - BUTT JOINT	SO YD	270	180	90
40600990	TEMPORARY RAMP	SO YD	60	30	30
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1,587	222	1365
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SO YD	16,239		16,239
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	180		180
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	320		320
48101200	AGGREGATE SHOULDERS, TYPE B	TON	153	16	137
67100100	MOBILIZATION	L SUM	1	0.3	0.7
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.3	0.7

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITY				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pvc\work\p\p\dot\k\k\l\l\g\k\d\0294597\78302-shite-cvr_sq_index.dgn		DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	JACKSON	16	5
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -		CONTRACT NO. 78302								
PLOT DATE = 3/23/2012		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								