

CHAMBLIN & ASSOCIATES, INC. © 2010
 C:\Users\jmc\Documents\11-00007-00-WR\11-00007-00-WR-01-Diamond-Will-County-IL-11-13-For-Survey\Drawings\11-00007-00-WR-01-Diamond-Will-County-IL-11-13-For-Survey-Plan-06-500.dwg
 Last Modified: Apr 11, 2012 - 11:47am
 Plotted on: Apr 11, 2012 - 12:01pm by rmcgib

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	PARTICIPATING	NON-PARTICIPATING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	118	118	—
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	140	140	—
20200100	EARTH EXCAVATION	CU YD	5199	4705	494
20400800	FURNISHED EXCAVATION	CU YD	2456	843	1613
20700220	POROUS GRANULAR EMBANKMENT	CU YD	136	136	—
20800150	TRENCH BACKFILL	CU YD	529	486	43
* 25000210	SEEDING, CLASS 2A	ACRE	1.76	1.11	0.65
* 25000310	SEEDING, CLASS 4	ACRE	0.82	0.82	—
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	235	176.8	58.2
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	235	176.8	58.2
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	235	176.8	58.2
Δ 25100115	MULCH, METHOD 2	ACRE	1.76	1.11	0.65
* 25100630	EROSION CONTROL BLANKET	SQ YD	4026	3983	43
* 25200110	SODDING, SALT TOLERANT	SQ YD	230	230	—
* 25200200	SUPPLEMENTAL WATERING	UNIT	14	14	—
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	525	396	129
28000305	TEMPORARY DITCH CHECKS	FOOT	24	0	24
28000400	PERMETER EROSION BARRIER	FOOT	1622	1418	204
28000500	INLET AND PIPE PROTECTION	EACH	11	10	1
28100107	STONE RIPRAP, CLASS A4	SQ YD	70	70	—
28200200	FILTER FABRIC	SQ YD	70	70	—
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	5879	3866	2013
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	24	0	24
35100100	AGGREGATE BASE COURSE, TYPE A	TON	1864	1720	144
35501315	HOT-MIX ASPHALT BASE COURSE, 7 3/4"	SQ YD	3645	2526	1119
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	85	85	—
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	224	193	31
Δ 40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2925	2320	605
40600300	AGGREGATE (PRIME COAT)	TON	51	33.1	17.9
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	2	1	1
40600535	LEVELING BINDER (HAND METHOD), N70	TON	3	2	1
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	255	255	—
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2265	1170	1095
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	373	179	194
40600990	TEMPORARY RAMP	SQ YD	40	26	14
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	334	334	—
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	374	374	—

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	PARTICIPATING	NON-PARTICIPATING
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	727	445	282
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	181	134	47
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	103	103	—
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	553	462	91
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2719	2106	613
42400800	DETECTABLE WARNINGS	SQ FT	330	248	82
44000100	PAVEMENT REMOVAL	SQ YD	1735	1735	—
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	879	879	—
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	348	233	115
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1306	1306	—
44000600	SIDEWALK REMOVAL	SQ FT	1703	1703	—
44004250	PAVED SHOULDER REMOVAL	SQ YD	631	296	335
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	21	21	—
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	220	220	—
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4150	2600	1550
Δ 48101200	AGGREGATE SHOULDERS, TYPE B	TON	126	85	41
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	411	0	411
50105220	PIPE CULVERT REMOVAL	FOOT	182	136	46
Δ 54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2	2	—
Δ 54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2	2	—
54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3'	FOOT	272	272	—
X5400903	PRECAST CONCRETE BOX CULVERTS 9' X 3' (SPECIAL)	FOOT	137	137	—
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	52	0	52
54213450	END SECTIONS 15"	EACH	2	0	2
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	7	3	4
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	—
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	—
54248510	CONCRETE COLLAR	CU YD	1.2	1.2	—
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	261	203	58
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	450	450	—
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	64	64	—
550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	65	65	—
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	61	61	—
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	61	61	—

* - SPECIALTY ITEM
 Δ - SPECIAL PROVISION

DRAWN BY: NV	REVISIONS			
CHECKED BY: JKC	LEVEL	BY	DATE	DESCRIPTION
DATE: 02/12				


CHAMBLIN & ASSOCIATES
 PERU MORRIS
 ILLINOIS

FAS 301 / FAU 383
 SECTION 11-00007-00-WR
 VILLAGE OF DIAMOND
 GRUNDY AND WILL COUNTIES

SUMMARY OF QUANTITIES

**CONSTRUCTION
 PLANS**

CONTRACT NO. 87520	
CURRENT AS OF: 02/12	
SCALE: AS NOTED	SHEET 6
FILE NO.: 66022.01 Y-	OF 96