

SUMMARY OF QUANTITIES

ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		ITEM NO.	SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
						ROADWAY 0004	STRUCTURE 0011							ROADWAY 0004	STRUCTURE 0011
1		20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	48		48	41	RSP	Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1
2		20200100	EARTH EXCAVATION	CU YD	97	97		42	SP, SI	Z0059700	SANITARY SEWER, TYPE 2 10"	FOOT	80		80
3		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	57		57	43	SP, SI	XX006199	STEEL BRIDGE RAIL, TYPE SM (SPECIAL)	FOOT	102		102
4		20700220	POROUS GRANULAR EMBANKMENT	CU YD	140		140								
5		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	166	166									
6		25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04									
7		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4									
8		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4									
9		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4									
10		25100115	MULCH, METHOD 2	ACRE	0.08	0.08									
11		25100630	EROSION CONTROL BLANKET	SQ YD	166	166									
12	BDE	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	16	16									
13		28000305	TEMPORARY DITCH CHECKS	FOOT	24	24									
14		28000400	PERIMETER EROSION BARRIER	FOOT	301	301									
15		28100109	STONE RIPRAP, CLASS A5	SQ YD	118		118								
16		28200200	FILTER FABRIC	SQ YD	118		118								
17	SP	30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	124	124									
18		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	55	55									
19	BDE	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	28	28									
20	BDE	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14	14									
21		42001300	PROTECTIVE COAT	SQ YD	20	20									
22		44000100	PAVEMENT REMOVAL	SQ YD	124	124									
23		44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	108	108									
24		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	88	88									
25	SP	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1								
26		50300300	PROTECTIVE COAT	SQ YD	172		172								
27		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	32400		32400								
28		51500100	NAME PLATES	EACH	1		1								
29		54003000	CONCRETE BOX CULVERTS	CU YD	193.3		193.3								
30		60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	88	88									
31	SI	63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	2	2									
32	SI	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2									
33		67100100	MOBILIZATION	L SUM	1		1								
34	SI	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	34	34									
35	RSP, SI	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8									
36	SI	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2									
37	SP	X0325323	MANHOLES, TYPE A, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1									
38	SP, SI	X0487700	SANITARY SEWER REMOVAL 10"	FOOT	80	80									
39	SP, SI	X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	1	1									
40	SP	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1									

SP=SPECIAL PROVISION RSP=RECURRING SPECIAL PROVISIONS SI=SPECIALITY ITEM BDE=BUREAU OF DESIGN AND ENVIRONMENT

FILE NAME = V:\3044\3044q001.dgn

USER NAME = bdeoraene	DESIGNED -	REVISED -
PLOT SCALE = 1.000' / IN.	DRAWN -	REVISED -
PLOT DATE = 3/27/2012	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DIVISION ST. SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA. N/A	TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	11-00692-00-DR	LA SALLE	15	3
FED. ROAD DIST. NO. 7 [ILLINOIS] FED. AID PROJECT BRM-5066(017)			CONTRACT NO. 87521	