

COMMITMENTS

Commitments are not to be altered without the written approval of all parties to which the commitment was made.

Parcel No. 408J285TE and 408J286TE

The existing masonry columns located on each side of each entrance to the funeral home (US 24 Station 918+40 to 919+70 Right) shall not be disturbed or damaged during construction.

Parcel No. 408J518-PE

The Engineer shall contact Dale Lyndsey (309-329-2606) one week before work begins to discuss the location of drainage tiles in his yard. The drainage tiles drain into the existing storm sewer east of Green St.

Parcel No. 408J238-PE (US 24 Sta. 893+03.64 Sta. 894+15.35 Lt)

- If the sidewalk leading to the house is disturbed, it will be fixed in kind.
- The retaining wall will be removed, but the yard and sidewalk within the easement area will be put back at a 5:1 slope or flatter.
- Any lawn area disturbed by the construction will be re-shaped and sodded.

Parcel 408J297-TE

The existing signs located at US 24 Station 4+82, 36' left shall not be damaged or removed.

Parcel 408J261-TE

The existing flag pole located at US 24 Station 906+89, 37' right, shall not be removed or damaged.

Parcel 408J313-TE

The existing granite monument at US 24 Station 12+33, 38' left, shall not be removed or damaged.

Parcel 408J519-TE

The resident engineer will contact Mr. and Mrs. Hayes at (309) 329-2352 15 days prior to the start of construction on their property. This notification will allow them to make any necessary arrangements to adjust for their son's health needs.

Post Office

Pedestrian access to the front door of the Post Office shall be maintained at all times.

Terry Lehman

Handicap access to the front door of Mr. Lehman's business, "Studio Screens," shall be maintained at all times. Any short-term closure shall be coordinated with Mr. Lehman.

FILE NAME = miscsheets.dgn	USER NAME = horstkj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>COMMITMENTS</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / 1" =	DRAWN -	REVISED -					317	16W-1, RS-3	FULTON	347	6
PLOT DATE = 3/13/2012	CHECKED -	REVISED -	CONTRACT NO. 88795									
	DATE -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	