

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FED.	80% STATE	50% STATE			
				20% STATE	20% TOWN	50% TOWN	100% TOWN	100% STATE	
				004	004	004	004	004	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	2000	2000					
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	3.1	2.7		0.2	0.2		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	583	583					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	347	347					
40600990	TEMPORARY RAMP	SQ YD	558	558					
40603212	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL - 12.5, N50	TON	698	698					
40603535	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	475	415		28	32		
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	81	81					
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SQ YD	27431	27431					
42001300	PROTECTIVE COAT	SQ YD	7514	7514					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1579	1579					
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1868	1868					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	37846	28131	9715				

FILE NAME =
schedule.sheets.dgn

USER NAME = boyer.mj
DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	16W-1, RS-3	FULTON	347	15
			CONTRACT NO. 88795	
ILLINOIS FED. AID PROJECT				