



SECTION AA

SIDEWALK ELEVATIONS - NORTH SIDE OF US 24 BETWEEN WALNUT ST. AND PEARL ST.

US 24 STATION	US 24 CENTERLINE ELEVATION	EDGE OF PAVT. ELEVATION "A"	TOP OF CURB ELEVATION "B"	BOTTOM OF FIRST STEP "C"	TOP OF FIRST STEP "D"	BACK OF FIRST STEP "E"	TOP OF SECOND STEP "F"	BACK OF SIDEWALK "G"
925+07.00	712.44	712.24	712.62	712.65	712.92	712.94	713.21	713.36
925+26.00	712.35	712.15	712.53	712.56	712.88	712.90	713.21	713.36
925+39.00	712.27	712.07	712.45	712.48	712.85	712.87	713.23	713.38
925+46.00	712.22	712.02	712.40	712.43	712.82	712.84	713.23	713.38
925+61.00	712.13	711.93	712.31	712.34	712.79	712.81	713.26	713.41
925+68.00	712.08	711.88	712.26	712.29	712.77	712.79	713.26	713.41
925+79.00	712.01	711.81	712.19	712.22	712.60	712.62	712.99	713.14
925+85.00	711.97	711.77	712.15	712.18	712.58	712.60	712.99	713.14
925+98.00	711.89	711.69	712.07	712.10	712.35	712.37	712.61	712.76
926+05.00	711.84	711.64	712.02	712.05	712.32	712.34	712.61	712.76
926+18.00	711.76	711.56	711.94	711.97	712.29	712.31	712.62	712.77
926+26.00	711.71	711.51	711.89	711.92	712.26	712.28	712.62	712.77
926+31.00	711.68	711.48	711.86	711.89	712.23	712.25	712.58	712.73
926+40.00	711.62	711.42	711.80	711.83	712.20	712.22	712.58	712.73
926+52.00	711.54	711.34	711.72	711.75	712.18	712.20	712.62	712.77
926+61.00	711.48	711.28	711.66	711.69	712.15	712.17	712.62	712.77
926+71.00	711.42	711.22	711.60	711.63	712.13	712.15	712.64	712.79
926+80.00	711.36	711.16	711.54	711.57	712.10	712.12	712.64	712.79

- NOTE: 1. WHERE HANDRAIL IS BEING INSTALLED IN THE BACK OF THE SIDEWALK, THE BACK 1' OF THE SIDEWALK SHALL BE CONSTRUCTED 6" THICK TO ALLOW FOR FASTENING OF THE HANDRAIL TO THE SIDEWALK.
2. NOSINGS OF STEPS SHALL HAVE 1/2" RADIUS (MAX).