

ITEM NUMBER	ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	358
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	207
20101100	TREE TRUNK PROTECTION	EACH	2
20200100	EARTH EXCAVATION	CU YD	6654
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	335
20700110	POROUS GRANULAR EMBANKMENT	TON	690
20800150	TRENCH BACKFILL	CU YD	1538
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	450
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	5285
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	65
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	65
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	65
25200100	SODDING	SQ YD	2241
25200110	SODDING, SALT TOLERANT	SQ YD	3044
25200200	SUPPLEMENTAL WATERING	UNIT	264
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	109
28000305	TEMPORARY DITCH CHECKS	FOOT	192
28000400	PERIMETER EROSION BARRIER	FOOT	185
28000500	INLET AND PIPE PROTECTION	EACH	6
28000510	INLET FILTERS	EACH	33
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	6898
35101400	AGGREGATE BASE COURSE, TYPE B	TON	697
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	9
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	711
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5609
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	602
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1964
40603230	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1840
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1051
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	43
42001300	PROTECTIVE COAT	SQ YD	3892
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	643
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	89
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	17464
42400800	DETECTABLE WARNINGS	SQ FT	156
44000100	PAVEMENT REMOVAL	SQ YD	7294
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1124
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1294
44000600	SIDEWALK REMOVAL	SQ FT	484
44003100	MEDIAN REMOVAL	SQ FT	1831
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SQ YD	31
5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	10
5421D030	PIPE CULVERTS, CLASS D, TYPE 1 30" (TEMPORARY)	FOOT	20
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	81
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	51
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	122
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	808
60107700	PIPE UNDERDRAINS 6"	FOOT	1283
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1
60221102	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	12
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	7
60500040	REMOVING MANHOLES	EACH	1

ITEM NUMBER	ITEM	UNIT	QUANTITY
60500060	REMOVING INLETS	EACH	5
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	3033
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	46
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15
67100100	MOBILIZATION	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	14
70300100	SHORT TERM PAVEMENT MARKING	FOOT	964
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16046
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2996
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4776
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	397
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	353
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	108
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	57
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	16
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	59
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	407
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	2500
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	2129
* 81400100	HANDHOLE	EACH	5
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	7500
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	17
* 82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1
* 83002600	LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. DAVIT ARM	EACH	17
* 83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	102
* 83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	17
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2591
* 87900200	DRILL EXISTING HANDHOLE	EACH	1
X0321690	BRICK WALL REMOVAL	FOOT	31
X5015225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	432
X6020065	INLETS, TYPE G-1, DOUBLE (SPECIAL)	EACH	5
X6020094	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1
X6020298	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1
X6021065	INLETS, TYPE G-1, SPECIAL	EACH	20
X6024503	INLETS TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)	EACH	3
X6060160	COMBINATION CONCRETE CURB AND GUTTER OUTLET, (SPECIAL)	EACH	2
X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	1360
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
XZ127902	RETAINING WALL, SPECIAL	SQ FT	12803
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0022800	FENCE REMOVAL	FOOT	1842
Z0034105	MATERIAL TRANSFER DEVICE	TON	1051
Z0056648	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	449
Z0056652	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 18"	FOOT	15
Z0056670	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18"	FOOT	118
Z0056672	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	29
XX000610	RELOCATE EXISTING MAILBOX	EACH	14
XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	149
XX006498	COMBINATION CONCRETE CURB AND SIDEWALK 4 INCH (SPECIAL)	SQ FT	2757
XX006598	VINYL FENCE, 6'	FOOT	174
XX008376	CONCRETE GUTTER FLAG	FOOT	393
Z0056668	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	363
Z0056678	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 36"	FOOT	86
Δ Z0076600	TRAINEES	HR	1000

* SPECIALTY ITEMS

Δ 0042

