

CROSS ROAD AND SIDE ROAD CULVERT SCHEDULE							
LOCATION	ALIGNMENT	54010302	54010402	54010403	542C0223	542C0229	542C0241
		PRECAST CONCRETE BOX CULVERT 3' X 2'	PRECAST CONCRETE BOX CULVERT 4' X 2'	PRECAST CONCRETE BOX CULVERT 4' X 3'	PIPE CULVERTS, CLASS C, TYPE 1 18"	PIPE CULVERTS, CLASS C, TYPE 1 24"	PIPE CULVERTS, CLASS C, TYPE 1 36"
STATION		UNIT FEET	UNIT FEET	UNIT FEET	UNIT FEET	UNIT FEET	UNIT FEET
STA. 287+81.00	COUNTY HIGHWAY #1		64.0				
STA. 317+35.50	COUNTY HIGHWAY #1			138.0			
STA. 327+82.50	COUNTY HIGHWAY #1	128.0					
STA. 359+85.25	COUNTY HIGHWAY #1		64.0				
STA. 372+14.30	COUNTY HIGHWAY #1					128.0	
STA. 1952+91.59	TR 1950 N						85.0
STA. 2000+38.00	TR 2000 N	75.0					
STA. 2102+27.00	TR 2100 N				72.0		
TOTAL		203.0	128.0	138.0	72.0	128.0	85.0

MOBILIZATION	67100100
LOCATION	UNIT
STATION	L SUM
ENTIRE JOB SITE	1.00
TOTAL	1.00

INLETS, TYPE A, TYPE 8 GRATE	60236200
LOCATION	UNIT
STATION	EACH
STA. 340+50.00, 21.0' RT	1.0
TOTAL	1.0

MANHOLE, TYPE A, 4' DIA., TYPE 8 GRATE	60219000
LOCATION	UNIT
STATION	EACH
STATION 383+68.00, 35.17' LT	1.0
TOTAL	1.0

STEEL END SECTIONS						
LOCATION	LT/RT	ALIGNMENT	54213870	54213873	54213879	54213891
			STEEL END SECTIONS 15"	STEEL END SECTIONS 18"	STEEL END SECTIONS 24"	STEEL END SECTIONS 36"
STATION			UNIT EACH	UNIT EACH	UNIT EACH	UNIT EACH
STA. 290+31.00	LT	COUNTY HIGHWAY #1	2			
STA. 290+89.50	RT	COUNTY HIGHWAY #1	2			
STA. 312+67.50	LT	COUNTY HIGHWAY #1	2			
STA. 315+00.00	RT	COUNTY HIGHWAY #1	2			
STA. 320+00.00	LT	COUNTY HIGHWAY #1	2			
STA. 330+80.00	LT	COUNTY HIGHWAY #1		2		
STA. 339+25.00, 32.0' RT	RT	COUNTY HIGHWAY #1	1			
STA. 343+76.10	LT	COUNTY HIGHWAY #1	2			
STA. 357+25.00	LT	COUNTY HIGHWAY #1	2			
STA. 357+67.50	RT	COUNTY HIGHWAY #1	2			
STA. 372+14.30	LT & RT	COUNTY HIGHWAY #1			2	
STA. 375+00.00	LT	COUNTY HIGHWAY #1	2			
STA. 375+00.00	RT	COUNTY HIGHWAY #1	2			
STA. 1952+91.59	LT & RT	TR 1950 N				2
STA. 2102+27.00	LT	TR 2100 N		1		
TOTAL			21	3	2	2

STORM SEWER SPECIAL (FEET)					
CONTINGENT QUANTITY FOR FIELD TILE REPLACEMENT DURING CONSTRUCTION					
6"	8"	10"	12"	15"	18"
61139900	61140000	61140100	61140200	61140400	61140600
300.0	300.0	300.0	300.0	300.0	300.0

BOX CULVERT END SECTIONS							
LOCATION	ALIGNMENT	SIZE	54001001	54001002	54001003	54001004	54001005
			BOX CULVERT END SECTIONS, CULVERT NO. 1	BOX CULVERT END SECTIONS, CULVERT NO. 2	BOX CULVERT END SECTIONS, CULVERT NO. 3	BOX CULVERT END SECTIONS, CULVERT NO. 4	BOX CULVERT END SECTIONS, CULVERT NO. 5
STATION		FOR INFO ONLY	UNIT	UNIT	UNIT	UNIT	UNIT
			EACH	EACH	EACH	EACH	EACH
STA. 287+81.00	COUNTY HIGHWAY #1	4'x2'	1				
STA. 317+35.50	COUNTY HIGHWAY #1	DOUBLE 4'x3'		4			
STA. 327+82.50	COUNTY HIGHWAY #1	DOUBLE 3'x2'			2		
STA. 359+85.25	COUNTY HIGHWAY #1	4'x2'				2	
STA. 2000+38.00	TR 2000 N	3'X2'					2
TOTAL			1	4	2	2	2

INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	60240215
LOCATION	UNIT
STATION	EACH
STA. 339+75.00, 21.0' RT	1.0
TOTAL	1.0

REVISIONS	
NAME	DATE
Δ	6-7-12