

CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY
20101100	TREE TRUNK PROTECTION	EACH	7
20101200	TREE ROOT PRUNING	EACH	7
20200100	EARTH EXCAVATION	CU YD	197
28000400	PERIMETER EROSION BARRIER	FOOT	482
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	12
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	247
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	13,735
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1,010
42400800	DETECTABLE WARNINGS	SQ FT	290
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	265
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	70
44000600	SIDEWALK REMOVAL	SQ FT	10,276
60255500	MANHOLES TO BE ADJUSTED	EACH	1
60600605	CONCRETE CURB, TYPE B	FOOT	394
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	70
67100100	MOBILIZATION	L SUM	1
72000100	SIGN PANEL - TYPE 1	SQ FT	6
72900100	METAL POST - TYPE A	FOOT	30
Δ *	88000105 FLASHING BEACON INSTALLATION	EACH	2
*	Z0013798 CONSTRUCTION LAYOUT	L SUM	1
*	X7010216 TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
*	XX007001 ROOT BARRIER	EACH	7

Δ SPECIALTY ITEMS

\* SPECIAL PROVISION

CONSTRUCTION TYPE CODE: 0021