

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				ST/EP ROADWAY 00 31 URBAN	NON 00 31 URBAN
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	11	11	
20800150	TRENCH BACKFILL	CU YD	57	46	11
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SO YD	1313	1313	
35300210	PORTLAND CEMENT CONCRETE BASE COURSE 7-1/2"	SO YD	244	244	
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SO YD	21	21	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.9		3.9
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	235		235
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	776		776
40603510	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	453		453
42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SO YD	620		620
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	462	462	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	89	89	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	10909	10909	
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SO FT	161	161	
42400800	DETECTABLE WARNINGS	SO FT	158	158	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	689	689	
44000300	CURB REMOVAL	FOOT	1481	1481	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	616	616	
44000600	SIDEWALK REMOVAL	SO FT	11693	11693	
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SO YD	159	159	
44213200	SAW CUTS	FOOT	887	887	
50200100	STRUCTURE EXCAVATION	CU YD	69	69	
50300225	CONCRETE STRUCTURES	CU YD	18	18	
50800105	REINFORCEMENT BARS	LB.	1110	1110	
50901760	PIPE HANDRAIL	FOOT	85	85	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	30		30
56500400	DOMESTIC METER VAULTS TO BE REMOVED	EACH	1	1	
56500600	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED	EACH	9	9	
60255500	MANHOLES TO BE ADJUSTED	EACH	14	1	13
60260100	INLETS TO BE ADJUSTED	EACH	2	2	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	9		9
60500060	REMOVING INLETS	EACH	3		3
60600605	CONCRETE CURB, TYPE B	FOOT	79	79	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1517	1517	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	604	604	
67100100	MOBILIZATION	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SO FT	132	132	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2	
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5	5	
72400710	RELOCATE SIGN PANEL - TYPE 1	SO FT	21	21	
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	859		859
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1881		1881
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	125		125
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	855		855
81028330	UNDERGROUND CONDUIT, PVC, 1 1/4" DIA.	FOOT	329	329	
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	3255	3255	
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	290	290	
81702110	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO.10	FOOT	11572	11572	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE
				ST/EP ROADWAY 00 31 URBAN	NON 00 31 URBAN
81702120	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO.8	FOOT	7408	7408	
81702130	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO.6	FOOT	4016	4016	
81702140	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO.4	FOOT	3998	3998	
82103600	LUMINAIRE, SODIUM VAPOR, VERTICAL MOUNT, 250 WATTS	EACH	4	4	
83012100	LIGHT POLE ALUMINUM 30' MH TENNON MOUNT	EACH	2	2	
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	11	11	
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	1	
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	5	5	
87800300	CONCRETE FOUNDATION, TYPE E, 24" DIA.	FOOT	10	10	
87900200	DRILL EXISTING HANDHOLE	EACH	1	1	
88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	1	1	
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	102	102	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	18	18	
A2001216	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	9	9	
A2004716	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	8	8	
B2000416	TREE, ACER GRISEUM (PAPERBARK MAPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	9	9	
B2003116	TREE, MALUS CORALBURST (CORALBURST CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	
B2005716	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	2	2	
B2006216	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	4	4	
LR430050	CONCRETE PAVEMENT SIDEWALK	SO YD	841	841	
X4003308	TRENCH DRAIN	FOOT	22	22	
X0325273	REMOVE AND REINSTALL VIDEO DETECTION CAMERA	EACH	1	1	
X0325981	RELOCATE EXISTING SIGNAL HEAD, SPECIAL	L SUM	1	1	
X0326820	INLETS, SPECIAL, TYPE E, 4'x4'	EACH	4		4
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	73	73	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	5155		5155
X4402400	CURB REMOVAL (SPECIAL)	FOOT	132	132	
X4404400	PAVEMENT REMOVAL (SPECIAL)	SO YD	313	313	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
X8040102	ELECTRIC SERVICE INSTALLATION (SPECIAL)	EACH	1	1	
X8130110	JUNCTION BOX (SPECIAL)	EACH	50	50	
X8250505	LIGHTING CONTROLLER, (SPECIAL)	EACH	1	1	
X8780107	CONCRETE FOUNDATION (SPECIAL)	FOOT	135	135	
XX007295	LIGHTING UNIT A, COMPLETE	EACH	34	34	
XX007296	LIGHTING UNIT B, COMPLETE	EACH	11	11	
Z0004002	BOLLARDS	EACH	2	2	

• SEE SPECIAL PROVISION
 Δ SPECIALTY ITEMS

FILE NAME =
 D6XXX-sh1-4-500

USER NAME = MDL
 PLOT SCALE = 1" = 40'
 PLOT DATE = #DATE#

DESIGNED - _____	REVISED - _____
DRAWN - _____	REVISED - _____
CHECKED - _____	REVISED - _____
DATE - _____	REVISED - _____

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: 1" = 20' SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. RTE. 63	SECTION 09-00309-00-LS	COUNTY ADAMS	TOTAL SHEETS 39	SHEET NO. 4
CONTRACT NO. 93578				
ILLINOIS FED. AID PROJECT				