

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	SURFACE TRANSPORTATION URBAN (STU)	NON PARTICIPATING
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2103	2103	
* 50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
50200100	STRUCTURE EXCAVATION	CU YD	87.8	71.2	16.6
50300225	CONCRETE STRUCTURES	CU YD	101.8	85.0	16.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	360.4	360.4	
50300260	BRIDGE DECK GROOVING	SQ YD	901	901	
50300280	CONCRETE ENCASEMENT	CU YD	56.5	43.4	13.1
50300300	PROTECTIVE COAT	SQ YD	1103	1103	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1	1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	14,690		14,690
50500505	STUD SHEAR CONNECTORS	EACH	3339	3339	
50800105	REINFORCEMENT BARS	POUND	6770		6770
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	98,730	95,950	2780
50800515	BAR SPLICERS	EACH	100	100	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	709	565	144
51201800	FURNISHING STEEL PILES HP14X73	FOOT	424	384	40
51202305	DRIVING PILES	FOOT	1133	949	184
51203600	TEST PILE STEEL HP12X53	EACH	1	1	
51203800	TEST PILE STEEL HP14X73	EACH	2	1	1
51500100	NAME PLATES	EACH	1	1	
51603000	DRILLED SHAFT IN SOIL	CU YD	37.8		37.8
52100505	ANCHOR BOLTS, 5/8"	EACH	24		24
52100520	ANCHOR BOLTS, 1"	EACH	58	42	16
542D1063	PIPE CULVERTS, CLASS D, TYPE 2 18"	FOOT	199	199	
54215553	METAL END SECTIONS 18"	EACH	8	8	

* DENOTES SPECIAL PROVISION

△ SPECIALTY ITEMS

FILE NAME =	USER NAME = Brian K. Nicholson	DESIGNED - MJP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED - KWB	REVISED -			7398	09-00905-00-BR	MACON	63	4	
		DRAWN - BKN	REVISED -			CONTRACT NO. 95687					
		CHECKED - KWB	REVISED -			SHEET NO. 2 OF 4 SHEETS					
						ILLINOIS FED. AID PROJECT					



345 EAST ASH AVENUE, SUITE B
 DECATUR, ILLINOIS 62526
 PH. 217-875-4800