

PAVEMENT AND SIDEWALK SCHEDULE

STATION	STATION	SIDE	ROADWAY	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2" (SQ YD)	AGGREGATE FOR TEMPORARY ACCESS (TON)	PAVEMENT FABRIC (SQ YD)	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH (SQ YD)	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH (SQ FT)	DETECTABLE WARNINGS (SQ FT)	CONCRETE CURB, TYPE B (FT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FT)	UTILITY PROTECTION PAD (SQ YD)	TREE GRATES (EACH)	CONCRETE MEDIAN (SPECIAL) (SQ FT)	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL (SQ FT)
4+58	5+46	RT	FERGUSON	11		11		738	19		77	3		4	440
4+58	5+45	LT	FERGUSON	16		16		625	16		77	3			306
5+78	6+59	RT	FERGUSON	16		16		565	17		75	3		6	454
5+79	12+66	LT	FERGUSON	26		26		4409	45		172	22		6	2180
6+59	6+80	RT	FERGUSON		10		17								
6+80	9+01	RT	FERGUSON					1466	16		18	8		4	561
9+28	12+66	RT	FERGUSON	15		15		2226	30		93	10			971
12+96	13+82	LT	FERGUSON	17		17		712	13		80	3			334
12+97	13+82	RT	FERGUSON	16		16		682	16		79	3			345
17+32	17+46	LT	S WOOD RIVER AVE	2		2		65	10		13				
17+32	17+47	RT	S WOOD RIVER AVE	2		2		55	9		12				
17+61	18+86	LT	S WOOD RIVER AVE	4		4		555	8		14	4			224
17+63	18+86	RT	S WOOD RIVER AVE					583	8		14	4			230
15+00	16+25	LT	SIDEWALK 3					1010	16						742
10+00	11+24	LT	SIDEWALK 4					1377	16	25			1		1680
			TOTAL	125	10	125	17	15068	239	25	724	63	1	20	8467

REMOVAL SCHEDULE

STATION	STATION	SIDE	ROADWAY	PAVEMENT REMOVAL (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	CURB REMOVAL (FT)	COMBINATION CONCRETE CURB AND GUTTER REMOVAL (FT)	SIDEWALK REMOVAL (SQ FT)	REMOVAL OF POLE FOUNDATION (EACH)
4+58	5+46	RT	FERGUSON	45			71	803	
4+58	5+45	LT	FERGUSON	48			72	794	
5+78	6+59	RT	FERGUSON	51			69	753	
5+79	6+09	LT	FERGUSON	48			78	274	
6+09	6+29	LT	FERGUSON		15				
6+29	12+66	LT	FERGUSON	44			88	5782	
6+59	6+80	RT	FERGUSON		17				
6+80	9+01	RT	FERGUSON				18	2103	
9+28	12+66	RT	FERGUSON	45			86	3037	
12+96	13+82	LT	FERGUSON	48			75	754	
12+97	13+82	RT	FERGUSON	50			73	785	
17+32	17+46	LT	S WOOD RIVER AVE	5		13		60	
17+32	17+47	RT	S WOOD RIVER AVE	5		12		49	
17+61	18+86	LT	S WOOD RIVER AVE	3			16	833	
17+63	18+86	RT	S WOOD RIVER AVE				14	854	
15+00	16+25	LT	SIDEWALK 3					1752	
10+00	11+24	LT	SIDEWALK 4			25		3094	1
			TOTAL	392	32	50	660	21727	1

TREE REMOVAL SCHEDULE

STATION	SIDE	ROADWAY	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT)
10+28	LT	SIDEWALK 4	24
		TOTAL	24

DRAINAGE STRUCTURES SCHEDULE

STRUCTURE NUMBER	STATION	OFFSET	SIDE	ROADWAY	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (EACH)	INLETS, TYPE A, TYPE 3 FRAME AND GRATE (EACH)	INLETS, TYPE A, TYPE 24 FRAME AND GRATE (EACH)	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID (EACH)	FILLING INLETS (EACH)
1	4+84	18.4	LT	FERGUSON		1			
3	5+29	19.9	LT	FERGUSON				1	
4	4+87	18.4	RT	FERGUSON		1			
6	5+29	19.6	RT	FERGUSON			1		
8	5+42	21.6	RT	FERGUSON			1		
9	5+84	23.0	RT	FERGUSON			1		
14	13+11	15.1	LT	FERGUSON		1			
16	13+57	18.3	LT	FERGUSON		1			
17	13+56	18.6	RT	FERGUSON		1			
19	13+20	19.5	RT	FERGUSON	1				
21	13+09	16.7	RT	FERGUSON			1		
24	5+15	19.0	LT	FERGUSON	1				
			TOTAL		2	5	3	1	1

STORM SEWERS SCHEDULE

STATION	STATION	SIDE	ROADWAY	TRENCH BACKFILL (CU YD)	STORM SEWERS, CLASS A, TYPE 1 12" (FT)	REMARKS
4+84	5+15	LT	FERGUSON	6.2	31	SN 1 TO SN 24
5+15	5+30	LT	FERGUSON	2.8	16	SN 24 TO EX MH
4+87	5+29	RT	FERGUSON	11.0	43	SN 4 TO SN 6
5+29	5+42	RT	FERGUSON	2.6	13	SN 6 TO SN 8
5+82	5+84	RT	FERGUSON	1.7	11	SN 11 TO SN 9
12+98	13+11	LT	FERGUSON	3.7	22	SN 12 TO SN 14
13+11	13+56	LT	FERGUSON	8.1	46	SN 14 TO SN 16
12+98	13+09	RT	FERGUSON	4.3	23	SN 23 TO SN 21
13+09	13+20	RT	FERGUSON	1.7	11	SN 21 TO SN 19
13+20	13+56	RT	FERGUSON	6.4	37	SN 19 TO SN 17
			TOTAL	48.5	253	

• FAU ROUTE 8971 & FAU ROUTE 9006
WOOD RIVER STREETScape PHASE 1