

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	44
S 20200100	EARTH EXCAVATION	CU YD	1,989
S 20800150	TRENCH BACKFILL	CU YD	623
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	1,144
25100630	EROSION CONTROL BLANKET	SO YD	85
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	80
28000305	TEMPORARY DITCH CHECKS	FOOT	23
28000400	PERIMETER EROSION BARRIER	FOOT	300
28000500	INLET AND PIPE PROTECTION	EACH	35
28100105	STONE RIPRAP, CLASS A3	SO YD	40
28200200	FILTER FABRIC	SO YD	40
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SO YD	3,634
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SO YD	178
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	300
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SO YD	351
40701841	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8"	SO YD	50
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SO YD	2,861
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	463
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	48
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	10,678
S 42400800	DETECTABLE WARNINGS	SO FT	50
44000100	PAVEMENT REMOVAL	SO YD	162
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	197
44000300	CURB REMOVAL	FOOT	24
44000600	SIDEWALK REMOVAL	SO FT	8,985
S 50105220	PIPE CULVERT REMOVAL	FOOT	257
50901760	PIPE HANDRAIL	FOOT	26
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
S 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	332
S 550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	8
S 550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	265
S 550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	366

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIES
S 550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	345
S 55100500	STORM SEWER REMOVAL 12"	FOOT	112
S 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	100
S 60100905	PIPE DRAINS 4"	FOOT	50
S 60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2
60219530	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	8
S 60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	13
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1
60240327	INLETS, TYPE B, TYPE 23 FRAME AND GRATE	EACH	7
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4
S 60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1
60500040	REMOVING MANHOLES	EACH	1
60600605	CONCRETE CURB, TYPE B	FOOT	20
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	2,253
67100100	MOBILIZATION	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	281
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	75
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	11
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	191
72000100	SIGN PANEL - TYPE 1	SO FT	12.0
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	4
72900100	METAL POST - TYPE A	FOOT	52
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	281
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	75
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	11
S Z0012450	CONCRETE STEPS	CU YD	4.0
S Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	165
S Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	40
S X2500930	SEEDING, CLASS 1B (MODIFIED)	ACRE	0.4
S X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
S X7240500	RELOCATE EXISTING SIGNS	EACH	1

NOTES:
 S SEE PROJECT SPECIFIC SPECIAL PROVISIONS
 • SPECIALTY ITEM