

PLAN	DATE
NO.	
BY	
DATE	
SURVEYED	DATE
ALIGNED	DATE
CHECKED	DATE
BY	
DATE	
NO.	
BY	
DATE	
NO.	

PROFILE	DATE
NO.	
BY	
DATE	
SURVEYED	DATE
ALIGNED	DATE
CHECKED	DATE
BY	
DATE	
NO.	
BY	
DATE	
NO.	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	SPECIAL
CODE NO.	ITEM	UNIT		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	△
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	102	△
20200100	EARTH EXCAVATION	CU YD	7171	△
20800150	TRENCH BACKFILL	CU YD	1238	
25000115	SEEDING, CLASS 1B	ACRE	2.8	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	252.2	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	252.2	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	252.2	
25100115	MULCH, METHOD 2	ACRE	2.8	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	5.6	
28000305	TEMPORARY DITCH CHECKS	FOOT	120	
28000400	PERIMETER EROSION BARRIER	FOOT	263	
28000500	INLET AND PIPE PROTECTION	EACH	56	
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	10096	
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	237	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1000	
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.7	
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	TON	8.1	
40300500	COVER COAT AGGREGATE	TON	43.4	
40300600	SEAL COAT AGGREGATE	TON	19.2	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1633.8	
40600300	AGGREGATE (PRIME COAT)	TON	17.1	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	115.4	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19, N70	TON	836.5	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	570.4	
42001300	PROTECTIVE COAT	SQ YD	822	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	423	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	306	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4 INCH	SQ FT	8665	
42400800	DETECTABLE WARNINGS	SQ FT	130	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	252	
44000300	CURB REMOVAL	FOOT	64	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	70	
44000600	SIDEWALK REMOVAL	SQ FT	1356	
50105220	PIPE CULVERT REMOVAL	FOOT	209	
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	112	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	72	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	SPECIAL
CODE NO.	ITEM	UNIT		
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	6	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	296	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	290	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	173	
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	679	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	402	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	222	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	383	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	609	
550A4900	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 24"	FOOT	155	
55100300	STORM SEWER REMOVAL 8"	FOOT	409	
55100700	STORM SEWER REMOVAL 15"	FOOT	106	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	10	
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	5	
60219570	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	1	
60222270	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	1	
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	5	
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	10	
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	
60500040	REMOVING MANHOLES	EACH	1	
60500060	REMOVING INLETS	EACH	3	
60600605	CONCRETE CURB, TYPE B	FOOT	146	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	3316	
60615400	PAVED DITCH, TYPE A-15	FOOT	213	
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	31.3	△
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	9	
67100100	MOBILIZATION	L SUM	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	153	
70300210	TEMPORARY PAVEMENT MARKING - LETTER AND SYMBOLS	SQ FT	125	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4424	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	245	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	79	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	SPECIAL
CODE NO.	ITEM	UNIT		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	51	
72000100	SIGN PANEL-TYPE 1	SQ FT	124.1	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	17	
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	10	
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	2	
72900100	METAL POST-TYPE A	FOOT	175.5	
72900200	METAL POST-TYPE B	FOOT	151.0	
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTER AND SYMBOLS	SQ FT	125	*
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	4424	*
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	333	*
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	79	*
X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	54	△
X0301339	REMOVE EXISTING PARKING BLOCKS	EACH	35	△
X0321158	PARK BENCHES	EACH	1	△
X0326519	STEEL RAILING REMOVAL	FOOT	286	△
X0350810	BOLLARD REMOVAL	EACH	3	△
X2010505	CLEARING, SPECIAL	L SUM	1	△
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	13	△
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	△
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	*
Z0050600	REMOVE AND RESET ORNAMENTAL FENCE	FOOT	78	△
Z0051398	REMOVE EXISTING SIGN POST	EACH	9	△

NOTE: * INDICATES SPECIALTY ITEM
NOTE: △ INDICATES SPECIAL PROVISION ITEM