

PAVEMENT/CURB & GUTTER REMOVAL SCHEDULE

LOCATION	SIDE	COMBINATION CURB AND GUTTER REMOVAL		CURB REMOVAL
		FOOT	FOOT	
EAST CENTRAL STREET				
123+69.69	LT			19
126+02.47	LT			24
127+91.48	LT			21
SUBTOTAL EAST CENTRAL STREET				64
EXISTING LONGFELLOW STREET				
600+21.70	TO	600+58.83	LT	42
600+26.19	TO	600+58.83	RT	28
SUBTOTAL EXISTING LONGFELLOW STREET				70
TOTAL				64

STRUCTURE REMOVAL/ADJUSTMENT ITEMS SCHEDULE

LOCATION	OFFSET	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID		
		REMOVING MANHOLES	REMOVING INLETS	
EAST CENTRAL STREET				
105+42.65	17.64' RT			1
105+56.88	30.41' LT			1
105+98.22	17.72' RT			1
108+08.59	10.80' LT	1		
109+70.80	15.99' RT		1	
112+08.13	11.72' LT	1		
113+56.37	19.43' LT	1		
SUBTOTAL (EAST CENTRAL STREET)				3
SUBTOTAL (EAST CENTRAL STREET)				3
TOTAL				3

DRIVEWAY PAVEMENT REMOVAL SCHEDULE

LOCATION	SIDE	TYPE	DRIVEWAY PAVEMENT REMOVAL	
			SQ YD	
EAST CENTRAL STREET				
107+97.90	LT	BIT		27
109+30.39	LT	CONC		15
119+24.25	LT	CONC		10
123+69.69	LT	BIT		83
126+02.47	LT	BIT		42
127+91.48	LT	BIT		40
130+12.27	LT	BIT		35
TOTAL				252

PARK BENCH SCHEDULE

LOCATION	SIDE	PARK BENCHES	
		EACH	
EAST MAIN STREET			
200+81.06	RT	1	
SUBTOTAL (EAST MAIN STREET)			1
TOTAL			1

PARKING BLOCK SCHEDULE

LOCATION	SIDE	REMOVE AND REINSTALL PARKING BLOCKS		REMOVE EXISTING PARKING BLOCKS	
		EACH	EACH	EACH	EACH
EAST CENTRAL STREET					
106+92.49	TO	112+63.00	RT	35	9
113+82.31			RT		26
115+01.45			LT	10	
SUBTOTAL (EAST CENTRAL STREET)				45	35
EAST MAIN STREET					
201+46.96			RT	9	
SUBTOTAL (EAST MAIN STREET)				9	
TOTAL				54	35

RAIL AND FENCE REMOVAL SCHEDULE

LOCATION	SIDE	STEEL RAILING REMOVAL		BOLLARD REMOVAL		REMOVE AND RESET ORNAMENTAL FENCE	
		FOOT	FOOT	EACH	EACH	FOOT	FOOT
EAST CENTRAL STREET							
114+96.96	TO	115+62.91	RT	180			
117+13.99			RT		1		
118+03.30			RT		1		
119+01.43			RT		1		
SUBTOTAL (EAST CENTRAL STREET)				180	3		
EAST MAIN STREET							
200+28.92	TO	201+15.94	RT	106			
201+01.63	TO	201.86.63	LT			78	
SUBTOTAL (EAST MAIN STREET)				106		78	
EAST LONGFELLOW STREET							
600+58.83							
SUBTOTAL (E LONGFELLOW STREET)							
TOTAL				286	3	78	

SIDEWALK REMOVAL SCHEDULE

LOCATION	SIDE	SIDEWALK REMOVAL		
		SQ FT		
EAST CENTRAL STREET				
105+40.37	TO	105+57.00	LT	69
110+17.74	TO	110+19.64	RT	81
110+99.48	TO	111+03.34	RT	73
111+89.01	TO	111+92.95	RT	70
111+91.91	TO	113+24.13	LT	574
123+69.69			LT	92
126+02.47			LT	109
127+91.48			LT	100
106+47.9	TO	106+57.92	LT	53
107+57.95	TO	107+65.85	LT	41
SUBTOTAL (EAST CENTRAL STREET)				1262
EAST MAIN STREET				
201+16.21	TO	201+28.11	LT	94
SUBTOTAL (EAST MAIN STREET)				94
TOTAL				1356

TREE REMOVAL SCHEDULE

LOCATION	SIDE	TREE REMOVAL	
		(6-15 UNIT DIAMETER)	(OVER 15 UNIT DIAMETER)
EAST CENTRAL STREET			
110+40.68	47.52' RT	6	
106+68.21	51.49' RT		18
106+92.40	51.66' RT		18
107+20.19	51.98' RT		36
SUBTOTAL (EAST CENTRAL STREET)		6	72
EX LONGFELLOW STREET			
601+90.35	21.75' LT		30
SUBTOTAL (EX LONGFELLOW STREET)			30
TOTAL		6	102

STORM SEWER/CULVERT REMOVAL SCHEDULE

LOCATION	STORM SEWER REMOVAL 8"		STORM SEWER REMOVAL 15"		PIPE CULVERT REMOVAL	
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
EAST CENTRAL STREET						
105+42.65	17.64' RT	TO	105+56.88,	30.41' LT		50
105+42.65	17.64' RT	TO	105+98.22	17.72' RT		56
105+98.22	17.72' RT	TO	105+98.20	31.93' RT		14
105+98.22	17.72' RT	TO	109+70.80	15.99' RT	373	
109+70.80	15.99' RT	TO	109+70.36	51.50' RT	36	
117+90.87	20.79' LT	TO	118+36.63	23.52' LT		43
119+06.46	21.82' LT	TO	119+36.09	20.76' LT		30
SUBTOTAL (EAST CENTRAL STREET)					409	106
EAST MAIN STREET						
200+90.30	12.95' LT	TO	201+04.42	15.12' RT		81
201+06.50	26.22' RT	TO	201+83.93	15.12' RT		41
SUBTOTAL (EAST MAIN STREET)						122
TOTAL					409	106

DATE: \_\_\_\_\_  
 BY: \_\_\_\_\_  
 SURVEYED \_\_\_\_\_  
 PLOTTED \_\_\_\_\_  
 CHECKED \_\_\_\_\_  
 PLAN NO. \_\_\_\_\_  
 DATE \_\_\_\_\_

DATE: \_\_\_\_\_  
 BY: \_\_\_\_\_  
 SURVEYED \_\_\_\_\_  
 PLOTTED \_\_\_\_\_  
 CHECKED \_\_\_\_\_  
 PROFILE NO. \_\_\_\_\_  
 DATE \_\_\_\_\_

08026-sht-Schedule.dwg

USER NAME = Robert Watson

DESIGNED - M.J.R.

REVISED -

PLOT SCALE =  
 CHECKED - E.R.O.  
 PLOT DATE = 3/21/2012

DRAWN - R.A.W.

REVISED -

DATE - 3/21/12

REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 6 OF 62 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8959	08-00026-00-WR	MADISON	62	6
CONTRACT NO. 97493				
BETHALTO		ILLINOIS FED. AID PROJECT		