

**SIGN SCHEDULE**

LOCATION	SIDE	TYPE (SIZE)	SIGN PANEL TYPE 1	METAL POST TYPE A	METAL POST TYPE B	STEEL PLATE BEAM GUARDRAIL
			SQ FT	FOOT	FOOT	FOOT
<b>EAST CENTRAL STREET</b>						
105+80.00	17.29' RT	R2-1 (30"x24")	5.0			
106+08.32	16.75' LT			12.5		
106+62.56	34.51' RT			12.5		
109+67.05	16.75' LT			12.5		
109+81.29	24.28' LT			15.0		
110+86.12	26.25' RT	W11-2 (30")	6.3		17.0	
		W16-2aP (24"x12")	2.0			
112+11.20	17.08' RT	W11-2 (30")	6.3		17.0	
		W16-7P (24"x12")	2.0			
112+34.80	24.98' RT	R7-8 (18"x9")	1.1	12.0		
		W11-2 (30")	6.3			
112+38.80	17.08' LT	W16-7P (24"x12")	2.0		17.0	
112+50.80	24.98' RT	R7-8 (18"x9")	1.1	10.0		
		W11-2 (30")	6.3			
113+28.00	17.09' LT	W16-2aP (24"x12")	2.0		17.0	
114+52.79	34.55' LT	R7-8 (18"x9")	1.1	12.0		
114+65.22	42.85' LT	R7-8 (18"x9")	1.1	12.0		
		W11-2 (30")	6.3			
114+82.65	16.55' RT	W16-2aP (24"x12")	2.0		17.0	
115+82.65	19.25' RT	W11-2 (30")	6.3	13.0		
		W16-7P (24"x12")	2.0			
116+93.46	25.08' LT	W11-2 (30")	6.3		17.0	
		W16-2aP (24"x12")	2.0			
117+06.96	18.00' RT			14.0		
117+93.46	25.14' LT	W11-2 (30")	6.3		17.0	
		W16-2aP (24"x12")	2.0			
120+05.70	25.00' LT			12.0		
<b>SUBTOTAL (EAST CENTRAL STREET)</b>			<b>75.8</b>	<b>137.5</b>	<b>119.0</b>	
<b>EAST MAIN STREET</b>						
200+40.45	18.97' LT	D3-1 (2 OF)	1.8	15.0		
		R1-1 (30")	6.3	13.0		
201+24.68	65.59' RT	R7-8 (18"x9")	1.1	10.0		
<b>SUBTOTAL (EAST MAIN STREET)</b>			<b>9.2</b>	<b>38.0</b>		
<b>EXISTING LONGFELLOW STREET</b>						
600+56.83	X	R11-2 (48"x30")	10			31.3
		OM4-1 (18"x18"), 2 OF	4.5			
<b>SUBTOTAL (EXISTING LONGFELLOW STREET)</b>			<b>14.5</b>			<b>31.3</b>
<b>LONGFELLOW STREET</b>						
400+32.23	21.69' LT	R1-1 (30")	6.3		16.0	
		D3-1 (2 OF)	6.0			
402+06.56	25.50' RT	R1-1 (30")	6.3		16.0	
		D3-1 (2 OF)	6.0			
<b>SUBTOTAL (LONGFELLOW STREET)</b>			<b>24.6</b>		<b>32.0</b>	
<b>TOTAL</b>			<b>124.1</b>	<b>175.5</b>	<b>151.0</b>	<b>31.3</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING				
		LETTERS AND SYMBOLS	4"	4"	6"	12"
		YELLOW	WHITE	YELLOW	WHITE	WHITE
<b>EAST CENTRAL STREET</b>						
105+12.97	TO 112+22.00	SOLID			1418	
112+28.00	TO 115+86.37	SOLID			719	
112+50.00	X	SOLID				52
112+83.00	RT	SOLID	50		255	
115+01.45	LT	SOLID	50	111	368	
115+89.92	X	SOLID				61
115+93.54	TO 120+00.00	SOLID			815	
<b>SUBTOTAL (EAST CENTRAL STREET)</b>			<b>100</b>	<b>111</b>	<b>3575</b>	<b>61</b>
<b>EAST MAIN STREET</b>						
200+38.09	TO 201+68.96	SOLID			262	14
200+30.58	X	SOLID				62
201+46.96	RT	SOLID	25		119	
<b>SUBTOTAL (EAST MAIN STREET)</b>			<b>25</b>		<b>381</b>	<b>62</b>
<b>LONGFELLOW STREET</b>						
402+06.90	RT	SOLID				13
400+21.58	X	SOLID				122
402+07.90	RT	MARKER				
400+29.08	TO 402+07.90	SOLID			357	
402+07.90		SOLID				13
<b>SUBTOTAL (LONGFELLOW STREET)</b>					<b>357</b>	<b>135</b>
<b>NORTH VINE STREET</b>						
900+15.87	TO 900+27.33	SOLID				75
<b>SUBTOTAL (NORTH VINE STREET)</b>						<b>75</b>
<b>TOTAL</b>			<b>125</b>	<b>111</b>	<b>4313</b>	<b>333</b>

**DETECTABLE WARNINGS**

LOCATION	SIDE	DETECTABLE WARNING SQ FT
<b>EAST CENTRAL STREET</b>		
105+49.03	LT	12
105+96.82	LT	12
109+82.03	LT	12
110+22.32	LT	12
112+25.00	LT	10
112+25.00	RT	10
115+87.54	LT	17
115+92.47	RT	10
116+62.78	LT	13
<b>SUBTOTAL (EAST CENTRAL STREET)</b>		<b>108</b>
<b>EAST MAIN STREET</b>		
200+30.43	RT	10
200+30.68	LT	12
<b>SUBTOTAL (EAST MAIN STREET)</b>		<b>22</b>
<b>TOTAL</b>		<b>130</b>

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU YD
EAST CENTRAL STREET 105+40 TO 112+15	1506	1130	274	856
EAST CENTRAL STREET 112+15 TO 121+00	3980	2985	112	2873
EAST MAIN STREET	809	607	13	594
LONGFELLOW STREET	876	657	0	657
<b>TOTAL</b>		<b>7171</b>	<b>5378</b>	<b>399</b>

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_ CHECKED: \_\_\_\_\_  
 ALIGNED: \_\_\_\_\_ CHECKED: \_\_\_\_\_  
 PLAN: \_\_\_\_\_ NO. \_\_\_\_\_  
 NOTE BOOK: \_\_\_\_\_  
 FILE NAME: \_\_\_\_\_

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 SURVEYED: \_\_\_\_\_ CHECKED: \_\_\_\_\_  
 PROFILE: \_\_\_\_\_ NO. \_\_\_\_\_  
 NOTE BOOK: \_\_\_\_\_  
 STRUCTURE: \_\_\_\_\_ NOTATIONS: \_\_\_\_\_