


SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	288	
AR401614	BIT. SURF. CSE.-METHOD II, SUPERPAV	TON	3,600	
AR401630	BITUMINOUS SURFACE TEST SECTION	EA.	1	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	14,464	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	178	
AR401915	REM & REP BIT PAVEMENT -- TYPE A	S.Y.	170	
AR510510	TIE DOWN	EA.	36	
AR510900	REMOVE TIE DOWN	EA.	66	
AR603510	BITUMINOUS TACK COAT	GAL.	5,063	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	6,313	
AE620525	PAVEMENT MARKING-BLACK BORDER	S.F.	5,752	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	660	
AR800534	CONSTRUCT PAVED CRICKET	S.Y.	118	
AR904510	SODDING	S.F.	288	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED HAUL ROUTE DETAIL
5	PROPOSED PAVEMENT PREPARATION PLAN
6	PROPOSED CONSTRUCTION PLAN
7	EXISTING AND PROPOSED TYPICAL SECTIONS
8	PROPOSED TYPICAL SECTIONS FOR CRICKETS
9	PROPOSED MARKING PLAN
10	PROPOSED MARKING COORDINATE TABLE

REVISION	DATE



DECATUR, ILLINOIS

IL PROJ.: DEC-4102 A.I.P. PROJ.: 3-17-0033-B3

Hanson Proj. No. 10A01360_0001
 Filename R-002ELP_1.DWG
 Scale NOT TO SCALE
 Date 05/11/12

LAYOUT	JSL	03/21/11
DRAWN	BAK	03/21/11
REVIEWED	RAW	04/07/11



© Copyright Hanson Professional Services Inc. 2012
Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Ph: (217) 788-2450 Fax: (217) 788-2503
 www.hanson-inc.com
 Offices Nationwide

RECONSTRUCT
 NORTH GA RAMP

SUMMARY OF QUANTITIES
 AND INDEX TO SHEETS