

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SIGNATURE SHEET
3	INDEX OF SHEETS, STANDARDS, GENERAL NOTES, STATION EQUATIONS, OMISSIONS
4	SUMMARY OF QUANTITIES
5 - 6	LOCATION MAPS
7	INTENTIONALLY LEFT BLANK
8	SCHEDULE OF QUANTITIES

GENERAL NOTES

FACTORS USED FOR QUANTITY CALCULATIONS ARE AS FOLLOWS:

JOINT SEALER 0.60 LB/FT

THE QUANTITY USED FOR CRACK FILLING IS AN ESTIMATE. THE ACTUAL AMOUNT USED WILL BE DETERMINED BY THE ENGINEER.

STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306-04	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH
701311-03	LANE CLOSURE, 2L, 2W, MOVING OPERATIONS - DAY ONLY
701501-06	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701901-07	TRAFFIC CONTROL DEVICES

△ REV. 6-6-2018

STATION OMISSIONS

IL 142 (HAMILTON COUNTY)			
STA.	470+66	TO	471+04
STA.	289+17	TO	290+03
STA.	266+27	TO	267+13
STA.	227+12	TO	227+78
IL 1 (WHITE COUNTY)			
STA.	119+90.35	TO	120+68.35
STA.	176+17.13	TO	177+71.13
STA.	335+97.65	TO	336+63.15
STA.	73+00	TO	103+95 (MEDIAN SECTION)
IL 142 (SALINE COUNTY)			
STA.	85+99	TO	87+01
STA.	159+05.4	TO	159+45.1
IL 13 (GALLATIN COUNTY)			
STA.	1688+83.5	TO	1691+35.5
IL 146 (HARDIN COUNTY)			
STA.	76+46	TO	77+14
STA.	278+90	TO	282+70
STA.	84+86.75	TO	86+16
STA.	227+67	TO	228+89

STATION EQUATIONS

IL 14 (HAMILTON COUNTY)	
STA. 925+52.4 BK	= STA. 14+00 AH
IL 142 (HAMILTON COUNTY)	
STA. 1+31.1 BK	= STA. 763+23.1 AH
IL 1 (WHITE COUNTY)	
STA. 336+86.1 BK	= STA. 100+00 AH
STA. 734+09.50BK	= STA. 110+70.32AH
STA. 66+75 BK	= STA. 778+30.97AH
STA. 849+29.6 BK	= STA. 4+93.03 AH
IL 142 (SALINE COUNTY)	
STA. 0+00 BK	= STA. 718+91 AH
IL 146 (HARDIN COUNTY)	
STA. 317+49 BK	= STA. 0+00 AH

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE: SHEET OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D9 CRACK SEAL 2019-1	VARIOUS	8	3
CONTRACT NO. 78648				
ILLINOIS FED. AID PROJECT				

THIS PAGE INTENTIONALLY LEFT BLANK

△ REVISED SHEET 6-6-2018

MODEL: Default
FILE NAME: D:\WORK\BIDDING\ILLINOIS\paw\PIV\DOT\Documents\DOT_Offices\District_9\Projects\Contract_Maint_2019\crack_sealing_various - to 922 & 942\CAD\Drawings\CD\Sheets\978648-Sheets.dgn

USER NAME = rollavr	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 6/5/2018	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCALE:	SHEET	OF	SHEETS	STA.	TO STA.
--------	-------	----	--------	------	---------

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D9 CRACK SEAL 2019-1	VARIOUS	8	7
CONTRACT NO. 78648				
ILLINOIS FED. AID PROJECT				

MODEL: D:\chart...
 FILE NAME: RW...
 PROJECT: ...
 DATE: 6/5/2018

LOCATION	ROUTE	COUNTY	STA.	TO	STA.	LENGTH (FT)	CENTER OF ROADWAY LONGITUDINAL CRACKS ONLY		COMMENTS
							CRACK ROUTING (FT)	CRACK FILLING (POUND)	
1	IL 14	HAMILTON	137+40	TO	14+00	12,340	12,340	7,404	2 LANES- 1 CENTERLINE JOINT
1	IL 14	HAMILTON	925+52	TO	580+28	34,524	34,524	20,715	2 LANES- 1 CENTERLINE JOINT
2	IL 142	HAMILTON	589+40	TO	1+31	58,533	58,533	35,120	2 LANES- 1 CENTERLINE JOINT
2	IL 142	HAMILTON	763+23	TO	708+08	5,515	5,515	3,309	2 LANES- 1 CENTERLINE JOINT
3	IL 1	WHITE	369+02	TO	336+86	3,216	3,216	1,930	2 LANES- 1 CENTERLINE JOINT
3	IL 1	WHITE	100+00	TO	734+10	63,112	63,112	37,867	2 LANES- 1 CENTERLINE JOINT
3	IL 1	WHITE	110+70	TO	66+75	1,300	1,300	780	2 LANES- 1 CENTERLINE JOINT
3	IL 1	WHITE	778+31	TO	849+30	7,099	7,099	4,259	2 LANES- 1 CENTERLINE JOINT
3	IL 1	WHITE	4+93	TO	12+39	745	745	447	2 LANES- 1 CENTERLINE JOINT
4	IL 142	SALINE	325+15	TO	+	32,515	32,515	19,509	2 LANES- 1 CENTERLINE JOINT
4	IL 142	SALINE	718+91	TO	710+00	749	749	449	2 LANES- 1 CENTERLINE JOINT
5	IL 13	GALLATIN	1819+06	TO	1600+09	21,645	21,645	12,987	2 LANES- 1 CENTERLINE JOINT
6	IL 146	HARDIN	+50	TO	317+45	31,247	31,247	18,748	2 LANES- 1 CENTERLINE JOINT
6	IL 146	HARDIN	+	TO	483+61	48,109	48,109	28,866	2 LANES- 1 CENTERLINE JOINT
TOTAL							320,650	192,390	

△ REV. 6-6-2018

△

USER NAME = rollavr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -					VAR.	D9 CRACK SEAL 2019-1	VARIOUS	8	8
PLOT DATE = 6/5/2018	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	
	DATE -	REVISED -		CONTRACT NO. 78645							