

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2005-040 GRR	WILL	18	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
CONTRACT 60A11				

HIGH TENSION CABLE GUARDRAIL

STA.	TO	STA.	DISCRIPTION	TOTAL LENGTH (FT.)
75+51.25	TO	88+40	66 POST SPACES AT 20'	1288.75
92+21.25	TO	142+70	254 POST SPACES AT 20'	5048.75
146+90	TO	163+98.75	87 POST SPACES AT 20'	1708.75
TOTAL				8046.25

HIGH TENSION CABLE GUARDRAIL TERMINAL

STA.	TO	STA.	DISCRIPTION	TOTAL LENGTH (FT.)	GRAND TOTAL LENGTH (FT.)	UNIT (EACH)
75+00	TO	75+18.75	3 POST SPACES AT 6'-3"	18.75	51.25	1
75+18.75	TO	75+51.25	5 POST SPACES AT 6'-6"	32.5		
88+40	TO	88+58.75	3 POST SPACES AT 6'-3"	18.75	51.25	1
88+58.75	TO	88+91.25	5 POST SPACES AT 6'-6"	32.5		
91+70	TO	91+88.75	3 POST SPACES AT 6'-3"	18.75	51.25	1
91+88.75	TO	92+21.25	5 POST SPACES AT 6'-6"	32.5		
142+70	TO	142+88.75	3 POST SPACES AT 6'-3"	18.75	51.25	1
142+88.75	TO	143+21.25	5 POST SPACES AT 6'-6"	32.5		
146+38.75	TO	146+57.5	3 POST SPACES AT 6'-3"	18.75	51.25	1
146+57.5	TO	146+90	5 POST SPACES AT 6'-6"	32.5		
163+98.75	TO	164+17.5	3 POST SPACES AT 6'-3"	18.75	51.25	1
164+17.5	TO	164+50	5 POST SPACES AT 6'-6"	32.5		
TOTAL					307.50	6

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**INTERSTATE 55
SCHEDULE OF QUANTITIES**

SCALE: VERT. : NONE
HORIZ. : NONE

DATE: _____ DRAWN BY: HMO
CHECKED BY: _____