

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2005-0771	COOK	14	4

CONTRACT: 60A83

LOCATION	COMB. CONC. C & G R&R (LF)	BIT. CONC.SURF R&R FULL DEPTH (SQ YD)	SIDEWALK 5" R&R (SQ FT) 18" CARRIAGE	SIDEWALK 5" R&R (SQ FT) 5' PARALLEL	DRIVEWAY 8" R&R (SQ FT)	SALT TOLERANT SODDING (SQ YD)	REMARKS
6158 S. MENARD	31.0	5.2	4.5	0.0	0.0	4.7	62ND ST SIDE
6105 S. MAJOR	19.0	3.2	0.0	0.0	0.0	3.2	
5731 W. 64TH PL.	5.0	0.8	3.0	0.0	0.0	0.5	
5451 W. 64TH PL.	15.0	2.5	0.0	0.0	0.0	2.5	PARKING LOT
5721 W. 64TH ST.	5.0	0.8	0.0	0.0	0.0	0.8	PARKING/PLAY LOT
5700 W. 63RD PL.	13.0	2.2	0.0	65.0	0.0	0.0	5' OF 13' IS HANDICAP WALK 8' SEC. CONTAINS TY23 STRUC.
5900 W. 63RD PL.	5.0	0.8	0.0	0.0	0.0	0.8	AROUND MEDIAN RADIUS
5901 W. 63RD ST.	8.0	1.3	0.0	0.0	0.0	1.3	AROUND ALLY RADIUS ON MAYFIELD AVE.
6426 S. LAPORTE	15.0	2.5	4.5	0.0	0.0	2.0	WRONG ADDRESS: SHOULD BE 6428 (NEW HOME)
6301 S. LACROSSE	5.0	0.8	0.0	0.0	0.0	0.0	ADJACENT TO BRICK PAVERS
6025 S. KILPATRICK	5.0	0.8	0.0	0.0	0.0	0.8	TY1 STRUC. IN FRONT OF CURB
6051 S. KEATING	5.0	0.8	3.8	0.0	0.0	0.4	
6225 S. KEATING	5.0	0.8	3.8	0.0	0.0	0.4	2 MINOR CRACKS
6149 S. KILBOURN	5.0	0.8	4.5	0.0	0.0	0.3	TY1 STRUC. IN FRONT OF CURB
6158 S. KILBOURN	10.0	1.7	4.5	0.0	0.0	1.2	
5638 S. KILBOURN	18.0	3.0	0.0	0.0	0.0	3.0	
5620 S. KILBOURN	5.0	0.8	0.0	0.0	0.0	0.8	
5515 S. KENNETH	10.0	1.7	0.0	0.0	0.0	1.7	TYPE 1 STRUCTURE
5744 S. KENNETH	5.0	0.8	7.5	0.0	0.0	0.0	
5743 S. KENNETH	10.0	1.7	15.0	0.0	0.0	0.0	
6453 S. KENNETH	6.0	1.0	9.0	0.0	0.0	0.0	TYPE 1 STRUCTURE
6342 S. KILDARE	5.0	0.8	3.8	0.0	0.0	0.4	IN FRONT OF PCC PATCH
6404 S. KILDARE	16.0	2.7	3.0	0.0	0.0	2.3	TYPE 1 STRUCTURE
6726 S. KILDARE	5.0	0.8	7.5	0.0	0.0	0.0	
6813 S. KILDARE	17.0	2.8	0.0	0.0	0.0	2.8	
6750 S. KOLIN	17.0	2.8	25.5	0.0	0.0	0.0	TYPE 1 STRUCTURE/SUNKEN CARRIAGE WALK
6715 S. KOLIN	19.0	3.2	24.8	0.0	0.0	0.4	TYPE 1 STRUCT./SUNKEN CARRIAGE WALK/ALLY RADIUS
6634 S. KOLIN	5.0	0.8	7.5	0.0	0.0	0.0	
6558 S. KOLIN	18.0	3.0	0.0	0.0	0.0	3.0	TYPE 1 STRUCTURE
6819 S. KOSTNER	34.0	5.7	51.0	0.0	0.0	0.0	ALREADY SAW CUT
6812 S. TRIPP	5.0	0.8	7.5	0.0	0.0	0.0	TYPE 1 STRUCTURE
6748 S. TRIPP	5.0	0.8	0.0	0.0	0.0	0.8	TYPE 1 STRUCTURE
SUB-TOTAL	351.0	58.5	190.5	65.0	0.0	34.3	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES