

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
VARIOUS	2005-0771	COOK	14	8

CONTRACT: 60A83

LOCATION	COMB. CONC. C & G R&R (LF)	BIT. CONC.SURF R&R FULL DEPTH (SQ YD)	SIDEWALK 5" R&R (SQ FT) 18" CARRIAGE	SIDEWALK 5" R&R (SQ FT) 5' PARALLEL	DRIVEWAY 8" R&R (SQ FT)	SALT TOLERANT SODDING (SQ YD)	REMARKS
7258 S. RIDGEWAY	5.0	0.8	7.5	0.0	0.0	0.0	2.5' CURB PAINTED YELLOW
7225 S. AVERS	6.0	1.0	9.0	0.0	0.0	0.0	
6950 S. LAWNSDALE	10.0	1.7	0.0	0.0	0.0	1.7	CURB NEAR CORNER
4151 W. 78TH PL.	10.0	1.7	0.0	50.0	0.0	0.0	
4141 W. 78TH PL.	42.0	7.0	0.0	150.0	18.0	0.0	
4348 W. 78TH ST.	9.0	1.5	0.0	0.0	0.0	1.5	9' FROM DRIVEWAY TO TY1 STRUC.
4210 W. 77TH PL.	10.0	1.7	0.0	0.0	0.0	1.7	
4224 W. 77TH PL.	12.0	2.0	0.0	0.0	10.5	0.8	
4338 W. 77TH PL.	5.0	0.8	0.0	0.0	0.0	0.8	
4349 W. 77TH PL.	5.0	0.8	0.0	0.0	0.0	0.8	CURB ADJACENT TO TY1 STRUC.
4434 W. 77TH PL.	10.0	1.7	0.0	0.0	1.5	1.5	CURB ADJACENT TO TY1 STRUC.
4544 W. 77TH PL.	16.0	2.7	0.0	0.0	16.5	0.8	
7700 S. KENTON	5.0	0.8	0.0	0.0	0.0	0.8	
7747 S. KENTON	11.0	1.8	0.0	0.0	4.5	1.3	TY1 STRUC. IN FRONT OF 8' SECT.
7805 S. KENTON	15.0	2.5	0.0	0.0	19.5	0.3	
7806 S. KENTON	10.0	1.7	0.0	0.0	15.0	0.0	CURB ADJACENT TO TY1 STRUC.
7817 S. KENTON	13.0	2.2	0.0	0.0	0.0	2.2	
7843 S. KENTON	5.0	0.8	0.0	0.0	0.0	0.8	
7748 S. KNOX	10.0	1.7	0.0	0.0	0.0	1.7	
7708 S. KNOX	14.0	2.3	0.0	0.0	0.0	2.3	CURB ADJACENT TO TY1 STRUC.
7724 S. KOLMAR	10.0	1.7	0.0	0.0	0.0	1.7	
7817 S. KOLMAR	5.0	0.8	0.0	0.0	0.0	0.8	CURB ADJACENT TO TY1 STRUC.
7717 S. KILBOURN	5.0	0.8	0.0	0.0	0.0	0.8	ON 77TH PL. SIDE OF HOUSE
7720 S. KILBOURN	5.0	0.8	0.0	0.0	0.0	0.8	
7804 S. KEELER	5.0	0.8	0.0	25.0	0.0	0.0	
7800 S. KEELER	10.0	1.7	0.0	50.0	0.0	0.0	
7814 S. KEELER	25.0	4.2	0.0	125.0	0.0	0.0	
7815 S. KEELER	5.0	0.8	0.0	25.0	0.0	0.0	
7826 S. KEELER	10.0	1.7	0.0	25.0	7.5	0.0	
7830 S. KEELER	13.0	2.2	0.0	65.0	0.0	0.0	
7838 S. KEELER	20.0	3.3	0.0	100.0	0.0	0.0	
7855 S. KEELER	15.0	2.5	0.0	75.0	0.0	0.0	
SUB-TOTAL	351.0	58.5	16.5	690.0	93.0	23.3	

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES