

CONTRACT: 60B12

F.A.D. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
559	500-R-1-3	COOK	---	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN 100% STATE SFTY-2A	
50102400	CONCRETE REMOVAL	CU YD	10.6	10.6	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.8	10.8	
50301200	CONCRETE WEARING SURFACE	SO YD	108.8	108.8	
50400605	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)	SO FT	1055	1055	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	760	760	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3600	3600	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	160	160	
X0320047	REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS	SO FT	844	844	
X0321781	MECHANICAL SPLICE	EACH	71	71	
X0322933	SILICONE JOINT SEALER, 2.5"	FOOT	102	102	
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	102	102	
Z0003900	BICYCLE RAILING	FOOT	70	70	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	8	8	
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	1	1	

© SFTY-3N

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	

PLOT DATE: 3/31/2006

3/31/2006 10:00 AM C:\p123\123050.dwg